

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			<b>COLD PLANING, BITUMINOUS PAVEMENT</b>
							14600				14600		CY	COMMON EXCAVATION	203.15	67	128585 SY		VT 105
							1200				1200		CY	EARTH BORROW	203.30	EST.	940 SY		TOWN HIGHWAYS
							5000				5000		CY	TRENCH EXCAVATION OF EARTH	204.20	48	129525 SY		SUBTOTAL
							530				530		CY	TRENCH EXCAVATION OF ROCK	204.21	EST.	475 SY		ROUNDING
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	130000 SY		TOTAL
							130000				130000		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	475			
							40900				40900		LF	MILLED RUMBLE STRIPS	213.10	35			
							38800				38800		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	90			
							9300				9300		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	23			
							147000				147000		SY	RECLAIMED STABILIZED BASE	310.20	351			
							3700				3700		TON	AGGREGATE SHOULDERS, RAP	402.13	18			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							26700				26700		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	222			
							1				1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-			
							1				1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-			
							1				1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-			
							1				1		LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-			
							2920				2920		LB	REINFORCING STEEL, LEVEL I	507.11	8			
									50		50		LF	REMOVAL OF EXISTING BRIDGE RAILING	525.10	-			
									50		50		LF	BRIDGE RAILING REPAIR, TYPE I	525.50	-			
							16				16		CY	CONCRETE, CLASS B	541.25	0.05			
							35				35		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415	2			
							15				15		LF	24" PCCSP .064 (2-2/3 X 1/2)	601.0425	3			
							3				3		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
							5				5		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-			
							16500				16500		LF	6 INCH UNDERDRAIN PIPE	605.10	190			
							55				55		HR	POWER GRADER RENTAL	608.15	EST.			
							900				900		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							40				40		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							1800				1800		HR	TRUCK RENTAL	608.37	EST.			
							30				30		HR	LOADER RENTAL, TYPE I	608.40	EST.			
							5800				5800		CY	STONE FILL, TYPE I	613.10	66			
							3700				3700		LF	BITUMINOUS CONCRETE CURB, TYPE A	616.305	11			
							8				8		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			
							1				1		EACH	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12	-			
							270				270		EACH	YIELDING MARKER POSTS	619.17	4			
							4175				4175		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	41.5			
							14250				14250		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	137.5			
							48				48		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			

PROJECT NAME: JAY-TROY  
PROJECT NUMBER: STP 2915(I)  
FILE NAME: z10b232frm.dgn PLOT DATE: 5/16/2014  
PROJECT LEADER: P. SHEDD DRAWN BY: W. GORDON  
DESIGNED BY: N. LEMAY CHECKED BY: P. SHEDD  
QUANTITY SHEET 1 SHEET 18 OF 244