LOCATION			DRAINAGE						CURB	GUARDRAIL								MISCELLANEOUS						REMARKS
			507.11	541.25	601.0415	601.0425	604.412	604.415	616.305	525.10	525.50	621.20	621.205	621.60	621.737	621.738	621.80	613.10	649.31	651.15	651.40	653.20	676.10	
MM	MM	POS	REINF. STEEL, LEVEL I	CONCRETE, CLASS B	18" PCCSP .064 (2-2/3 X 1/2)	24" PCCSP .064 (2-2/3 X 1/2)	REHAB. DI, CB, OR MH, CLASS I	REHAB. DI, CB, OR MH, CLASS II	BIT. CONCRETE CURB, TYPE A	REMOVAL OF EXIST. BRIDGE RAILING	BRIDGE RAILING REPAIR, TYPE I	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8' POSTS	ANCHOR FOR STEEL BEAM RAIL	GUARDRAIL APPROACH SECTION, GALV. HD STEEL BEAM	GUARDRAIL APPROACH SECTION, GALV. HD STEEL BEAM W/8' POSTS	REMOVAL & DISPOSAL OF GUARDRAIL	STONE FILL, TYPE I	GEOTEXT. UNDER STONE FILL	SEED	GRUBBING MATERIAL (6")	TEMP. EROSION MATTING	DELIN. W/ STEEL POST	
			LB	CY	LF	LF	EACH	EACH	LF	LF	LF	LF	LF	EACH	EACH	EACH	LF	CY	SY	LB	SY	SY	EACH	
35+90.0	442+25.0	LT/RT					3	5												35.0		15020		ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
35+90.0	442+25.0	LT/RT																5509	24802	12.5		1714		SEE DITCH CLEANING DETAIL SHEET
38+62.0	45+20.0	LT															658.0							
38+57.0	45+19.5	LT										29.0	637.5	2									2	SEE STANDARD G-1d
51+03.0	53+89.0	LT															286.0							
51+00.0	54+50.0	LT										354.0		2									2	SEE STANDARD G-1d
53+70.0		RT	516	2.85		6																		SEE STANDARD D-33
58+26.0	60+58.0	LT															232.0							
58+20.0	60+82.5	LT										266.5		2									2	SEE STANDARD G-1d
59+78.0	60+79.0	RT															101.0							
63+87.0	69+33.0	LT															546.0							
76+84.0	81+10.0	LT															426.0							
76+85.0	81+10.0	LT										429.0		2									2	SEE STANDARD G-1d
78+05.0		RT	376	2.05	6																			SEE STANDARD D-33
82+13.0		RT	516	2.85		6																		SEE STANDARD D-33
83+94.0	85+97.0	LT															203.0							
83+95.0	85+95.0	LT										29.0	175.0	2									2	SEE STANDARD G-1d
84+79.0	86+19.0	RT															140.0							
89+50.0	90+50.0	RT																18	53	1.0	52	52		
92+50.0	94+20.0	LT															170.0							
92+50.0	94+50.0	LT										204.0		2									2	SEE STANDARD G-1d
93+22.0	94+08.0	RT															86.0							
93+20.0	94+07.5	RT										91.5		2									2	SEE STANDARD G-1d
101+54.0	108+41.0	RT															687.0							
101+52.0	108+39.5	RT										29.0	662.5	2									2	SEE STANDARD G-1d
101+58.0	109+72.0	LT															814.0							
101+57.5	110+20.0	LT										866.5		2									2	SEE STANDARD G-1d
102+60.0	107+95.0	LT							535.0															
107+00.0	107+50.0	RT																13	32	0.5	32	32		
109+50.0	110+00.0	RT																10	29	0.5	29	29		
114+50.0	115+00.0	RT																9	27	0.5	27	27		
119+00.0	121+00.0	RT																32	97	2.0	97	97		
120+34.0	127+00.0	LT															666.0							
120+25.0	127+00.0	LT										79.0	600.0	2									2	SEE STANDARD G-1d
125+50.0	126+50.0	RT																16	47	1.0	47	47		
126+16.0		RT	376	2.05	6																			SEE STANDARD D-33
SUBTOTAL SHEET 21			1784	9.80	12	12	3	5	535.0			2377.5	2075.0	20			5015.0	5607	25087	53.0	284	17018	20	

PROJECT NAME: JAY-TROY
PROJECT NUMBER: STP 2915(1)

FILE NAME: z10b232frm.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
ITEM DETAIL SHEET I

PLOT DATE: 5/16/2014
DRAWN BY: W. GORDON
CHECKED BY: P. SHEDD
SHEET 21 OF 244