

TEMPORARY 4 INCH WHITE LINE, PAINT  
 DURABLE 4 INCH WHITE LINE, POLYUREA  
 408+50 TO 413+00 SOLID LT  
 408+50 TO 413+09 SOLID RT  
 413+00 TO 413+06 SOLID LT (TH 16)  
 413+09 TO 413+53 SOLID RT (TH 4)  
 413+27 TO 413+55 SOLID LT (TH 16)  
 413+73 TO 413+84 SOLID RT (TH 4)  
 413+55 TO 414+50 SOLID LT  
 413+84 TO 414+50 SOLID RT

TEMPORARY 4 INCH YELLOW LINE, PAINT  
 DURABLE 4 INCH YELLOW LINE, POLYUREA  
 408+50 TO 413+10 SOLID LT & RT  
 413+17 TO 413+29 DOUBLE SOLID LT (TH 16)  
 413+54 TO 413+63 DOUBLE SOLID RT (TH 4)  
 413+75 TO 414+50 SOLID LT & RT

TEMPORARY 24 INCH STOP BAR, PAINT  
 DURABLE 24 INCH STOP BAR (OPTION BID ITEM)  
 413+14 TO 413+30 LT (TH 16)  
 413+55 TO 413+71 RT (TH 4)

TEMPORARY LETTER OR SYMBOL, PAINT  
 DURABLE LETTER OR SYMBOL (OPTION BID ITEM)  
 413+20 LT - "STOP" (TH 16)  
 413+64 RT - "STOP" (TH 4)

STEEL BEAM GUARDRAIL, GALVANIZED  
 411+62.5 TO 411+75 LT  
 413+25.5 TO 413+38 RT

STEEL BEAM GUARDRAIL,  
 GALVANIZED W/8 FEET POSTS  
 408+50 TO 411+62.5 LT  
 408+50 TO 413+25.5 RT

ANCHOR FOR STEEL BEAM RAIL  
 2 (SEE STANDARD G-1d)

REMOVAL AND DISPOSAL OF GUARDRAIL  
 408+50 TO 411+01 LT  
 408+50 TO 413+35 RT

DELINEATOR WITH STEEL POST  
 411+75 LT  
 413+38 RT

MILLED RUMBLE STRIPS  
 408+50 TO 413+10 CL  
 413+75 TO 414+50 CL

PROJECT DEMARCATION FENCE  
 408+90 TO 410+50 LT

REMOVING SIGNS  
 AS SHOWN - 9

