LOCATION			DROP INLETS		GUARDRAIL																		REMARKS
			604.412	604.415	525.10	525.50	525.60	616.35	621.20	621.205	621.207	621.21	621.60	621.70	621.71	621.76	621.77	621.80	621.81	676.10	676.12			
STATION	STATION	POS.	.	.	REMOVAL OF EXIST. BRIDGE RAILING	BRIDGE RAILING REPAIR, TYPE I	BRIDGE RAILING REPAIR, TYPE II	TREATED TIMBER CURB	.	.	.	.	.	.	.	.	REPLACE GUARDRAIL BEAM UNIT	REMV. & DISP. OF GUARDRAIL	REMV. & DISP. OF GUIDE POSTS	DEL IN. W/STEEL POST	REMOVAL OF EXIST. DEL IN.			
			EACH	EACH	LF	LF	LF	LF					EACH	EACH	EACH	EACH	EACH	LF	EACH	EACH	EACH			
MAJOR COLLECTOR																								
0+38.0	62+08.0	LT/RT	8	2												3	2							ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
0+36.0	1+33.0	LT																97.0						
0+36.0	0+67.3	LT										31.3												BRIDGE APPROACH RAIL SCHEDULE II, SEE DETAIL ON SHEET 26
0+67.3	1+29.8	LT							64.5				1							1	1			ANCHOR @ 1+29.8, SEE STANDARD G-1D
0+36.0	1+01.0	RT																65.0						
0+36.0	0+67.3	RT										31.3												BRIDGE APPROACH RAIL SCHEDULE II, SEE DETAIL ON SHEET 26
0+67.3	1+04.8	RT							39.5				1											ANCHOR @ 1+04.8, SEE STANDARD G-1D
1+01.0	3+80.0	RT																279.0						
1+01.0	3+76.0	RT								309.0			2							2	2			ANCHOR@ 1+01, ANCHOR@ 3+76, SEE STANDARD G-1D, SEE NON-YIELDING OBJECT
																								DETAIL ON SHEET 33 FOR POST SPACING
36+52.0	36+79.0	LT																	7					
36+85.0	47+02.0	LT																1017.0						REMOVE CABLE GUARDRAIL
36+65.0	47+02.5	LT							1041.5				2							2	2			ANCHOR @ 36+65, ANCHOR @ 47+02.5, SEE STANDARD G-1D
39+31.0	46+92.0	RT																761.0						REMOVE CABLE GUARDRAIL
38+90.0	46+90.0	RT							804.0				2							2	2			ANCHOR @ 38+90, ANCHOR @ 46+90, SEE STANDARD G-1D
55+83.0	58+33.0	LT																250.0						
55+80.0	61+17.5	LT							541.5				2							2	2			ANCHOR @ 55+80, ANCHOR @ 61+17.5, SEE STANDARD G-1D
56+06.0	58+42.0	RT																236.0						
54+35.0	58+47.5	RT							416.5				2							2	2			ANCHOR @ 54+35, ANCHOR @ 58+47.5, SEE STANDARD G-1D
	US 5																							
U 69+71	U 70+94	RT																						RETAIN STEEL BEAM GUARDRAIL
U 72+57	U 73+27	LT																						RETAIN STEEL BEAM GUARDRAIL
SUBTOTAL SHEET 22			8	2					2907.5	309.0		62.6	12			3	2	2705.0	7	11	11			

ITEM DETAIL SUMMARY SHEET 1

PROJECT NAME: BRADFORD

PROJECT NUMBER: STP 2917(1)

FILE NAME: p10b236.dgn
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: p10b236_22

PLOT DATE: 03-SEP-2014 12:49
DRAWN BY: WWG
CHECKED BY: PTS
SHEET 22 OF 105