

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	ROADWAY (NO FED/ STATE PART)	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITY	UNIT	ITEMS
							2				2		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	-			COLD PLANING, BITUMINOUS PAVEMENT
							5				5		CY	COMMON EXCAVATION	203.15	1.6	17009	SY	VT 25B
							200				200		CY	EARTH BORROW	203.30	-	1217	SY	TOWN HIGHWAYS
							145				145		LF	SHOULDER BERM REMOVAL	203.40	3	18226	SY	SUBTOTAL
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	74	SY	ROUNDING
							18300				18300		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	74	18300	SY	TOTAL
							570				570		TON	SUBBASE, RAP	301.40	1.8			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
							360				360		TON	AGGREGATE SHOULDERS, RAP	402.13	3	1503	TON	VT 25B, TYPE IV S, WEARING COURSE
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	493	TON	VT 25B, TYPE IV S, LEVELING COURSE
							2110				2110		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	8	106	TON	TOWN HIGHWAYS, TYPE IV S
							1				1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	2102	TON	SUBTOTAL
							1				1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-	8	TON	ROUNDING
							1				1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-	2110	TON	TOTAL
									50		50		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	2			
									10		10		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.			
							10				10		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.			
							3				3		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.			
										14	14		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-			
							20				20		HR	POWER GRADER RENTAL	608.15	EST.			
							70				70		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							20				20		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							140				140		HR	TRUCK RENTAL	608.37	EST.			
							70				70		HR	LOADER RENTAL, TYPE I	608.40	EST.			
							90				90		CY	STONE FILL, TYPE I	613.10	1			
							35				35		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1.4			
							25				25		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	1			
							80				80		SF	DETECTABLE WARNING SURFACE	618.30	2			
							10				10		EACH	YIELDING MARKER POSTS	619.17	EST.			
							875				875		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	9			
							8				8		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
							2				2		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	EST.			
							2				2		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	EST.			
							850				850		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	5.5			
										9	9		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
							170				170		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							600				600		HR	FLAGGERS	630.15	EST.			
										0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10	-			PROJECT NAME: BRADFORD
										0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			PROJECT NUMBER: STP 2918(I)
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			FILE NAME: p10b236.dgn
							0.5				0.5		LS	MOBILIZATION/DEMobilIZATION	635.11	-			PLOT DATE: 03-SEP-2014 12:51
																			DRAWN BY: WWG
																			CHECKED BY: PTS
																			IPARM FILE NAME: p10C238_84
																			SHEET 84 OF 105