

COMPOSITE QUANTITY SHEET 1

	SUMMARY OF ESTIMATED QUANTITIES STP 2926 (1)				SUMMARY OF ESTIMATED QUANTITIES STP 027-1 (22)		TOTALS		DESCRIPTIONS			
	ROADWAY	TRAINING	BRIDGE ITEMS	FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND
	1						1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-
	3						3		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	-
	20				2740		2760		CY	COMMON EXCAVATION	203.15	-
	1130						1130		CY	EARTH BORROW	203.30	-
					1230		1230		CY	GRANULAR BORROW	203.32	-
	3200				250		3450		CY	TRENCH EXCAVATION OF EARTH	204.20	-
	840				24		864		CY	TRENCH EXCAVATION OF ROCK	204.21	-
	1				1		2		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
	161200						161200		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-
	12540						12540		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	-
					1090		1090		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	-
	173000						173000		SY	RECLAIMED STABILIZED BASE	310.20	-
	2000						2000		TON	AGGREGATE SHOULDERS, RAP	402.13	-
	1						1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
	34200				300		34500		CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	-
	20200				170		20370		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	-
	1						1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	1						1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
	1						1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
	1						1		LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
					2000		2000		LB	REINFORCING STEEL, LEVEL 1	507.11	-
			50				50		LF	REMOVAL OF EXISTING RAILING	525.10	-
			50				50		LF	BRIDGE RAILING REPAIR, TYPE 1	525.50	-
					20		20		CY	CONCRETE, CLASS B	541.25	-
										BEGIN OPTION AA		
					64		64		LF	42" CAAP .105 (2-2/3 X 1/2)	601.0252	-
					64		64		LF	42" PCCSP .109 (2-2/3 X 1/2)	601.0452	-
										END OPTION AA		
	20						20		LF	15" CPEP (SL)	601.2610	-
	3						3		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS 1	604.412	-
	14600				350		14950		LF	6 INCH UNDERDRAIN PIPE	605.10	-
					3		3		EACH	UNDERDRAIN FLUSHING BASIN	605.95	-
	70				5		75		HR	POWER GRADER RENTAL	608.15	-
	500				5		505		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE 1	608.25	-
	50				5		55		HR	POWER BROOM RENTAL, TYPE 1	608.30	-
	600				5		605		HR	TRUCK RENTAL	608.37	-
	45				5		50		HR	LOADER RENTAL, TYPE 1	608.40	-

PROJECT NAME: CAMBRIDGE-BAKERSFIELD & FLETCHER
PROJECT NUMBER: STP 2926(1) & STP 027-1(22)
FILE NAME: p11b064.dgn PLOT DATE: 11/15/2012
PROJECT LEADER: JLL DRAWN BY: STANTEC
DESIGNED BY: STANTEC CHECKED BY: JLL
IPARM FILE: 11b064cqs01.i SHEET 3 OF 387