

# COMPOSITE QUANTITY SHEET 2

	SUMMARY OF ESTIMATED QUANTITIES STP 2926 (1)				SUMMARY OF ESTIMATED QUANTITIES STP 027-1 (22)		TOTALS		DESCRIPTIONS				
	ROADWAY	TRAINING	BRIDGE	ITEMS	FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND
	7300					20		7320		CY	STONE FILL, TYPE I	613.10	-
						375		375		CY	STONE FILL, TYPE II	613.11	-
						145		145		CY	STONE FILL, TYPE III	613.12	-
	56							56		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-
	1							1		EACH	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12	-
	240							240		EACH	YIELDING MARKER POSTS	619.17	-
	675							675		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-
	9800					200		10000		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-
	150							150		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215	-
	200							200		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.217	-
						3		3		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-
	45					1		46		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-
	10700					180		10880		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
						360		360		LF	TEMPORARY TRAFFIC BARRIER	621.90	-
	1580					200		1780		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-
	6900					400		7300		HR	FLAGGERS	630.15	-
					1			1		LS	FIELD OFFICE, ENGINEERS	631.10	-
					1			1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-
					1			1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
					3000			3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
	1040							1040		HR	EMPLOYEE TRAINEESHIP	634.10	-
	1							1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1		1		LS	TRAFFIC CONTROL (STP 027-1 (22))	641.10	-
	1							1		LS	TRAFFIC CONTROL (STP 2926 (1))	641.10	-
	3							3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
											BEGIN OPTION BB		
	100700					900		101600		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	-
	100700					900		101600		LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	-
	100700					900		101600		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	-
											END OPTION BB		
											BEGIN OPTION CC		
	91200					900		92100		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	-
	91200					900		92100		LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	-
	91200					900		92100		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	-
											END OPTION CC		
											BEGIN OPTION DD		
	35							35		LF	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	646.442	-

PROJECT NAME: CAMBRIDGE-BAKERSFIELD & FLETCHER  
PROJECT NUMBER: STP 2926(1) & STP 027-1(22)  
FILE NAME: p11b064.dgn  
PROJECT LEADER: JLL  
DESIGNED BY: STANTEC  
IPARM FILE: 11b064cqs02.i  
PLOT DATE: 11/15/2012  
DRAWN BY: STANTEC  
CHECKED BY: JLL  
SHEET 4 OF 387