STATE OF VERMONT
AGENCY OF TRANSPORTATION

COMPOSITE QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES STP 2926(1)				SUMMARY OF ESTIMATED QUANTITIES STP 027-1(22)		TOTALS		DESCRIPTIONS			
ROADWAY	TRAINING	BRIDGE ITEMS	FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND
2400						2400		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-
7						7		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-
200						200		EACH	REMOVING SIGNS	675.50	-
45				1		46		EACH	DELINEATOR WITH STEEL POST	676.10	-
33						33		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-
				1		1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40	-
1						1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
				180		180		CY	SPECIAL PROVISION (DRAINAGE AGGREGATE)	900.608	-
2						2		EACH	SPECIAL PROVISION (SOIL BEARING SLIP BASE) (2 1/2")	900.620	-
				1		1		LS	SPECIAL PROVISION (TEMPORARY ROADWAY WIDENING) (SITE 1)	900.645	-
				1		1		LS	SPECIAL PROVISION (TEMPORARY ROADWAY WIDENING) (SITE 2)	900.645	-
183200				1460		184660		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	-
1860				15		1875		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	-
183200						183200		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	-
57000				470		57470		TON	SPECIAL PROVISION (MATERIAL TRANSFER DEVICE)	900.680	-
2770						2770		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	-
690				10		700		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	-
2400				15		2415		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	-
2280						2280		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	-

PROJECT NAME: CAMBRIDGE-BAKERSFIELD & FLETCHER
PROJECT NUMBER: STP 2926(1) & STP 027-1(22)

FILE NAME: p11b064.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: 11b064cqs04.i

PLOT DATE: 11/15/2012
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 6 OF 387