

BAKE 1

DIRECTION	ACTUAL GRID POINTS		PROJECT SPECIFIC COORDINATE POINTS
	METRIC	ENGLISH	
N	248816.886 m	816328.366 ft	816328.366 ft
E	474227.590 m	1555864.797 ft	1555864.797 ft
Z	161.120 m	528.61 ft	528.61 ft

GENERAL LOCATION, BAKERSFIELD, VT.

TO REACH FROM THE INTERSECTION OF VT ROUTES 36 AND 108 IN BAKERSFIELD, GO SOUTH ALONG VT ROUTE 108 FOR 1.7 MI (2.7 KM) TO THE INTERSECTION OF WHITNEY ROAD RIGHT. CONTINUE SOUTH ALONG VT ROUTE 108 FOR 1.5 MI (2.4 KM) TO THE SITE OF THE MARK ON THE RIGHT. IT IS ABOUT 37 M (121.4 FT) NORTH OF JORDAN ROAD RIGHT AND MILE MARKER POST 1080/0601/0038.

THE MARK IS SET 10 CM (4 INCHES) BELOW GROUND SURFACE IN THE TOP OF A FENO STYLE MONUMENT.

IT IS 7.0 M (23.0 FT) NORTHWEST OF AND ABOUT 0.1 M (0.3 FT) HIGHER THAN THE CENTERLINE OF VT ROUTE 108, 13.7 M (44.9 FT) SOUTH-SOUTHWEST OF POLE NO 14, 14.6 M (47.9 FT) SOUTH-SOUTHWEST OF MAILBOX NO 3275, 33.1 M (108.6 FT) NORTHEAST OF POLE NO 6/71 AND 0.3 M (1.0 FT) SOUTHEAST OF A FIBERGLASS WITNESS POST.

DESCRIPTIONS PROVIDED BY VERMONT AGENCY OF TRANSPORTATION GEODETIC SURVEY UNIT.

BAKE 2

DIRECTION	ACTUAL GRID POINTS		PROJECT SPECIFIC COORDINATE POINTS
	METRIC	ENGLISH	
N	249174.563 m	817501.848 ft	817501.850 ft
E	474388.935 m	1556394.142 ft	1556394.110 ft
Z	164.985 m	541.29 ft	541.30 ft

GENERAL LOCATION, BAKERSFIELD, VT

TO REACH FROM THE INTERSECTION OF VT ROUTES 36 AND 108 IN BAKERSFIELD, GO SOUTH ALONG VT ROUTE 108 FOR 1.7 MI (2.7 KM) TO THE INTERSECTION OF WHITNEY ROAD RIGHT. CONTINUE SOUTH ALONG VT ROUTE 108 FOR 1.3 MI (2.1 KM) TO THE SITE OF THE MARK ON THE RIGHT. IT IS ABOUT 50 M (164.0 FT) NORTH OF THE SOUTHERN INTERSECTION OF GAMBLER ROAD LEFT.

THE MARK IS SET 10 CM (4 INCHES) BELOW GROUND SURFACE IN THE TOP OF A FENO STYLE MONUMENT.

IT IS 6.2 M (20.3 FT) WEST OF AND ABOUT 0.3 M (1.0 FT) LOWER THAN THE CENTERLINE OF VT ROUTE 108, 49.6 M (162.7 FT) NORTH OF AND ACROSS THE ROAD FROM A STOP SIGN AND MILE MARKER POST 1080/0601/0061, 37.6 M (123.4 FT) SOUTHWEST OF AND ACROSS THE ROAD FROM POLE NO 6/60 AND 0.3 M (1.0 FT) EAST OF A FIBERGLASS WITNESS POST.

TENNYSON

DIRECTION	ACTUAL GRID POINTS		PROJECT SPECIFIC COORDINATE POINTS
	METRIC	ENGLISH	
N	250766.629 m	822725.159 ft	822725.159 ft
E	474614.289 m	1557133.493 ft	1557133.493 ft
Z	200.740 m	658.60 ft	658.60 ft

GENERAL LOCATION, BAKERSFIELD, VT

TO REACH FROM THE INTERSECTION OF VT ROUTES 36 AND 108 IN BAKERSFIELD, GO SOUTH ALONG VT ROUTE 108 FOR 1.7 MI (2.7 KM) TO THE INTERSECTION OF WHITNEY ROAD RIGHT. CONTINUE SOUTH ALONG VT ROUTE 108 FOR 0.2 MI (0.3 KM) TO THE SITE OF MARK ON THE RIGHT IN A FIELD.

THE MARK IS SET IN THE TOP OF A MASSIVE ROCK OUTCROP WHICH PROJECTS 3.0 M (9.8 FT) ABOVE GROUND SURFACE.

IT IS 50.7 M (166.3 FT) NORTHWEST OF AND ABOUT 2.0 M (6.6 FT) HIGHER THAN THE CENTERLINE OF VT ROUTE 108, 59.4 M (194.9 FT) NORTH OF POLE NO 26/94/42, 70.0 M (229.7 FT) EAST OF A 140 CM (55 INCH) MAPLE THE CENTER TREE IN A ROW OF THREE, 14.3 M (46.9 FT) SOUTH OF A HAWTHORNE CLUMP, 35.5 M (116.5 FT) WEST OF POLE NO 95/41 AND A FIBERGLASS WITNESS POST.

DATUM	
VERTICAL	NAVD 88
HORIZONTAL	NAD 83 (07)
ADJUSTMENT	NONE

NOT TO SCALE

NOTE: ALL DIMENSIONS ARE IN FEET UNLESS NOTED OTHERWISE.



PROJECT TIE SHEET #3

PROJECT NAME: CAMBRIDGE-BAKERSFIELD
PROJECT NUMBER: STP 2926(1)

FILE NAME: p10b258.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10b258ct03.i

PLOT DATE: 11/15/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 10 OF 387