LOCATION					UNDERDRAIN				MISC. ITEMS		REMARKS
					204.20	204.21	605.10	619.17	*	*	
PIPE NO.	OUTLET INVERT	BEGIN STA.	END STA.	POS.	TRENCH EXCAVATION OF EARTH	TRENCH EXCAVATION OF ROCK	6 INCH UNDERDRAIN PIPE	YIELDING MARKER POSTS	DRAINAGE AGGREGATE	GEOTEXTILE FABRIC	
					CY	CY	LF	EA	CY	SY	
	VT ROUTE 108										
	BAKERSFIELD (CONT.)										
UD-36	626.1	84+00	87+00	LT	66	17	300	1	80	396	
UD-37	627.1	84+00	87+00	RT	66	17	300	1	80	396	
UD-38	666.5	93+65	96+50	LT	62	16	285	1	76	376	
UD-39	651.2	99+50	100+45	RT	17	5	95	1	20	114	
UD-40	647.0	100+55	102+67	RT	45	12	212	1	54	275	
UD-41	647.8	103+00	113+00	RT	234	59	1000	1	285	1361	
UD-42	695.2	114+00	116+00	RT	42	11	200	1	51	259	
UD-43	686.5	118+46	120+48	LT-RT	44	11	222	1	54	282	
UD-44	686.3	121+00	122+32	RT	26	7	132	1	31	165	
UD-45	627.9	125+50	132+50	RT	162	41	700	1	197	948	
UD-46	682.9	169+00	174+00	LT	114	29	500	1	139	672	
SHEET 19 SUBTOTALS					878	225	3946	11	1067	5244	
SHEET 18 SUBTOTALS					2295	598	10415	34	2813	13784	
ROUNDING					27	17	239	-	20	172	
TOTALS					3200	840	14600	45**	3900*	19200*	

INSTALLED AS PER PLAN

*SEE UNDERDRAIN DETAIL ON PREVIOUS SHEET

**TOTAL CARRIED FORWARD TO ITEM DETAIL SUMMARY SHEET

NOT TO SCALE

Stantec

UNDERDRAIN DETAIL SHEET #2

PROJECT NAME: CAMBRIDGE-BAKERSFIELD

PROJECT NUMBER: STP 2926(I)

FILE NAME: p10b258.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10b258unds02.i

PLOT DATE: 11/15/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 19 OF 387