STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMAINS REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
BAKERSFIELD CONT.																																				
171+10, RT	Bakersfield Exeeberg Falls 9	1	30	18	3.75						1					X		X																	99	
173+30, RT	SPEED LIMIT 40	1	30	36	7.50						1					X		X															R2-1	X		
173+30, LT	SPEED LIMIT 50	1	24	30	5.00						1					X		X															R2-1	X		
179+52, LT	1080 0601 0340	1	6	10	0.42						1				X			X															VD-700			E-138
184+27, RT	SPEED LIMIT 35	1	30	36	7.50						1					X		X															R2-1	X		
184+27, LT	SPEED LIMIT 40	1	24	30	5.00						1					X		X															R2-1	X		
	SHEET TOTAL				29.17										10	75																				
	SHEET 81 SUBTOTALS				70.43											77							3	290											
	SHEET 82 SUBTOTALS				60.32										23	60							2	122	153										
	SHEET 83 SUBTOTALS				78.03											62	73						2	168											
	SHEET 84 SUBTOTALS				41.25										50	50	60																		
	SHEET 85 SUBTOTALS				33.52										96	83																			
	SHEET 86 SUBTOTALS				54.10										36	150																			
	SHEET 87 SUBTOTALS				21.92										126	45																			
	SHEET 88 SUBTOTALS				45.42										37	112	17																		
	SHEET 89 SUBTOTALS				19.18										84	67																			
	SHEET 90 SUBTOTALS				32.01										50	90																			
	SHEET 91 SUBTOTALS				50.51											123																			
	SHEET 92 SUBTOTALS				46.92										22	165																			
	SHEET 93 SUBTOTALS				47.59										50	138																			
	SHEET 94 SUBTOTALS				52.93										42	106	20																		
	SHEET 95 SUBTOTALS				33.17										76	78	20																		
	SHEET 96 SUBTOTALS				29.17										10	75																			
	PROJECT SUBTOTALS				716.47										702	1481	190						7	580	153										
	ROUNDING				3.53										3	19	5						-	5	2										
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
															705	1500	195							585	155										
	TOTALS				SF 720	SF	EA.	SF				FT			FT 2400					LB			EA. 7	LB 740				EA.	EA.	LB					

"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #16

PROJECT NAME: CAMBRIDGE-BAKERSFIELD
PROJECT NUMBER: STP 2926(I)

FILE NAME: p10b258.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10b258tss16.i

PLOT DATE: 11/15/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 96 OF 387