

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Rotation Direction	Maximum Banking	Design Speed
Tangent	PT	669+97.27	801319.48	1554986.57						
	PC	671+16.56	801422.42	1554926.29						
Arc	PC	671+16.56	801422.42	1554926.29						
	PI	672+47.45	801535.37	1554860.15						
	CC		802028.77	1555961.83	1200	260.76	12°27'01"	Right	0.070	50
	PT	673+77.31	801659.93	1554819.92						
Tangent	PT	673+77.31	801659.93	1554819.92						
	PC	681+40.56	802386.23	1554585.32						
Arc	PC	681+40.56	802386.23	1554585.32						
	PI	683+06.91	802544.53	1554534.19						
	CC		802724.34	1555632.07	1100	330.20	17°11'56"	Right	0.073	50
	PT	684+70.76	802710.86	1554532.15						
Tangent	PT	684+70.76	802710.86	1554532.15						
	PC	686+82.25	802922.34	1554529.56						
Arc	PC	686+82.25	802922.34	1554529.56						
	PI	688+65.19	803105.27	1554527.32						
	CC		802903.36	1552979.68	1550	364.20	13°27'45"	Left	0.060	50
	PT	690+46.45	803282.65	1554482.56						
Tangent	PT	690+46.45	803282.65	1554482.56						
	PC	691+60.82	803393.54	1554454.57						
Arc	PC	691+60.82	803393.54	1554454.57						
	PI	693+05.35	803533.67	1554419.20						
	CC		803834.01	1556199.85	1800	288.43	9°10'52"	Right	0.055	50
	0	693+82.00	803610.78	1554413.74	Cambridge 693+84.48 BK = Fletcher 0+00.00 AHD					
	0	0+00.00	803610.78	1554413.74						
	PT	0+67.25	803677.65	1554406.65						
Tangent	PT	0+67.25	803677.65	1554406.65						
	PC	4+52.30	804061.25	1554373.20						
Arc	PC	4+52.30	804061.25	1554373.20						
	PI	10+29.31	804636.08	1554323.08						
	CC		803953.54	1553137.89	1240	1080.11	49°54'29"	Left	0.069	50
	PT	15+32.41	804967.93	1553851.05						
Tangent	PT	15+32.41	804967.93	1553851.05						
	PC	25+22.08	805537.12	1553041.44						
Arc	PC	25+22.08	805537.12	1553041.44						
	PI	26+64.55	805619.06	1552924.90						
	CC		817808.04	1561668.41	15000	284.92	1°05'18"	Right	NC	50
	PT	28+07.00	805703.19	1552809.93						
Tangent	PT	28+07.00	805703.19	1552809.93						
	PC	28+28.42	805715.84	1552792.65						
Arc	PC	28+28.42	805715.84	1552792.65						
	PI	32+53.25	805966.73	1552449.81						
	CC		806490.55	1553359.59	960	799.92	47°44'29"	Right	0.080	50
	PT	36+28.34	806389.18	1552404.96						
Tangent	PT	36+28.34	806389.18	1552404.96						
	PC	36+36.59	806397.39	1552404.08						
Arc	PC	36+36.59	806397.39	1552404.08						
	PI	40+07.22	806765.94	1552364.95						
	CC		806496.65	1553338.83	940	706.06	43°02'12"	Right	0.061	50
	PT	43+42.66	807062.03	1552587.87						
Tangent	PT	43+42.66	807062.03	1552587.87						
	PC	51+50.97	807707.79	1553074.04						
Arc	PC	51+50.97	807707.79	1553074.04						
	PI	53+98.49	807905.53	1553222.92						
	CC		804700.43	1557068.52	5000	494.64	5°40'05"	Right	0.022	50
	PT	56+45.61	808087.60	1553390.60						
Tangent	PT	56+45.61	808087.60	1553390.60						
	PC	65+41.83	808746.85	1553997.73						
Arc	PC	65+41.83	808746.85	1553997.73						
	PI	68+92.83	809005.04	1554235.51						
	CC		809729.13	1552931.13	1450	688.76	27°12'58"	Left	0.063	50
	PT	72+30.59	809343.40	1554328.89						
Tangent	PT	72+30.59	809343.40	1554328.89						
	PC	80+87.94	810169.86	1554556.96						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Rotation Direction	Maximum Banking	Design Speed
Arc	PC	80+87.94	810169.86	1554556.96						
	PI	84+25.55	810495.31	1554646.77						
	CC		811021.12	1551472.26	3200	672.73	12°02'43"	Left	0.035	50
	PT	87+60.68	810832.33	1554666.68						
Tangent	PT	87+60.68	810832.33	1554666.68						
	PC	101+26.08	812195.36	1554747.24						
Arc	PC	101+26.08	812195.36	1554747.24						
	PI	108+51.98	812920.00	1554790.06						
	CC		811924.87	1559324.25	4585	1439.85	17°59'34"	Right	0.026	50
	PT	115+65.94	813595.97	1555054.63						
Tangent	PT	115+65.94	813595.97	1555054.63						
	0	123+11.16	814289.93	1555326.25	Fletcher 123+12.96 BK = Bakersfield 0+00.00 AHD					
	0	0+00.00	814289.93	1555326.25						
	PC	2+43.76	814516.93	1555415.09						
Arc	PC	2+43.76	814516.93	1555415.09						
	PI	4+69.78	814727.39	1555497.47						
	CC		815573.89	1552714.57	2900	451.12	8°54'46"	Left	0.038	50
	PT	6+94.88	814948.08	1555546.24						
Tangent	PT	6+94.88	814948.08	1555546.24						
	PC	15+14.93	815748.81	1555723.20						
Arc	PC	15+14.93	815748.81	1555723.20						
	PI	16+01.87	815833.70	1555741.97						
	CC		813590.84	1565487.59	10000	173.87	0°59'46"	Right	NC	50
	PT	16+88.80	815918.25	1555762.20						
Tangent	PT	16+88.80	815918.25	1555762.20						
	PC	18+09.24	816035.38	1555790.23						
Arc	PC	18+09.24	816035.38	1555790.23						
	PI	20+91.60	816309.99	1555855.95						
	CC		815653.69	1557385.19	1640	559.24	19°32'16"	Right	0.048	50
	PT	23+68.48	816546.81	1556009.72						
Tangent	PT	23+68.48	816546.81	1556009.72						
	PC	27+03.54	816827.83	1556192.19						
Arc	PC	27+03.54	816827.83	1556192.19						
	PI	30+11.58	817086.18	1556359.94						
	CC		817582.08	1555030.58	1385	606.20	25°04'39"	Left	0.053	50
	PCC	33+09.74	817391.27	1556402.37						
	PCC	33+09.74	817391.27	1556402.37						
	PI	34+70.77	817550.77	1556424.56						
	CC		817646.14	1554570.02	1850	321.25	9°56'58"	Left	0.054	50
	PT	36+30.99	817711.70	1556418.85						
Tangent	PT	36+30.99	817711.70	1556418.85						
	PC	46+38.58	818718.65	1556383.15						
Arc	PC	46+38.58	818718.65	1556383.15						
	PI	46+97.85	818777.88	1556381.05						
	CC		817939.11	1534396.97	22000	118.53	0°18'31"	Left	NC	50
	PT	47+57.11	818837.09	1556378.63						
Tangent	PT	47+57.11	818837.09	1556378.63						
	PC	50+04.34	819084.12	1556368.54						
Arc	PC	50+04.34	819084.12	1556368.54						
	PI	50+68.95	819148.68	1556365.90						
	CC		819696.38	1571356.04	15000	129.21	0°29'37"	Right	NC	50
	PT	51+33.56	819213.25	1556363.82						
Tangent	PT	51+33.56	819213.25	1556363.82						
	PC	61+51.09	820230.25	1556331.05						
Arc	PC	61+51.09	820230.25	1556331.05						
	PI	64+04.28	820483.31	1556322.89						
	CC		820276.41	1557763.31	1433	501.22	20°02'25"	Right	0.051	50
	PT	66+52.30	820723.85	1556401.95						
Tangent	PT	66+52.30	820723.85	1556401.95						
	PC	75+60.49	821586.63	1556685.53						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Rotation Direction	Maximum Banking	Design Speed
Arc	PC	75+60.49	821586.63	1556685.53						
	PI	78+11.79	821825.36	1556763.99						
	CC		820930.92	1558680.53	2100	500.21	13°38'51"	Right	0.042	50
	PT	80+60.71	822038.84	1556896.57						
Tangent	PT	80+60.71	822038.84	1556896.57						
	PC	82+15.06	822169.97	1556978.01						
Arc	PC	82+15.06	822169.97	1556978.01						
	PI	84+18.00	822342.37	1557085.08						
	CC		806342.58	1582463.17	30000	405.88	0°46'31"	Right	NC	50
	PT	86+20.94	822513.30	1557194.47						
Tangent	PT	86+20.94	822513.30	1557194.47						
	PC	89+35.48	822778.24	1557364.01						
Arc	PC	89+35.48	822778.24	1557364.01						
	PI	92+45.09	823039.02	1557530.90						
	CC		825203.85	1553573.71	4500	618.25	7°52'18"	Left	0.026	50
	PT	95+53.73	823320.20	1557660.50					</	