

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	EROSION CONTROL	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS
				2740		2740	CY	COMMON EXCAVATION	203.15	6			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
				1230		1230	CY	GRANULAR BORROW	203.32	12	70	TON	SITE 1, WEARING COURSE TYPE IVS
				250		250	CY	TRENCH EXCAVATION OF EARTH	204.20	2	57	TON	SITE 2, WEARING COURSE TYPE IVS
				24		24	CY	TRENCH EXCAVATION OF ROCK	204.21	-	23	TON	SITE 1, LEVELING COURSE TYPE IVS
				1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	19	TON	SITE 2, LEVELING COURSE TYPE IVS
				1090		1090	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	7	1	TON	ROUNDING
				300		300	CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	29.5	170	TON	TOTAL
				170		170	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	1			STONE FILL, TYPE II
				2000		2000	LB	REINFORCING STEEL, LEVEL I	507.11	20	346	CY	SITE 1 STONE SLOPE REINFORCEMENT
				20		20	CY	CONCRETE, CLASS B	541.25	3.6	24	CY	SITE 2 DRAINAGE
								BEGIN OPTION AA			5	CY	ROUNDING
				64		64	LF	42" CAAP .105 (2-2/3 X 1/2)	601.0252	-	375	CY	TOTAL
				64		64	LF	42" PCCSP .109 (2-2/3 X 1/2)	601.0452	-			
								END OPTION AA					
				350		350	LF	6 INCH UNDERDRAIN PIPE	605.10	-			
				3		3	EACH	UNDERDRAIN FLUSHING BASIN	605.95	-			
				5		5	HR	POWER GRADER RENTAL	608.15	EST.			
				5		5	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
				5		5	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
				5		5	HR	TRUCK RENTAL	608.37	EST.			
				5		5	HR	LOADER RENTAL, TYPE I	608.40	EST.			
				20		20	CY	STONE FILL, TYPE I	613.10	4			
				375		375	CY	STONE FILL, TYPE II	613.11	5			
				145		145	CY	STONE FILL, TYPE III	613.12	3			
				200		200	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	10.5			
				3		3	EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			
				1		1	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
				180		180	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	1.2			
				360		360	LF	TEMPORARY TRAFFIC BARRIER	621.90	7			
				200		200	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
				400		400	HR	FLAGGERS	630.15	EST.			
				1		1	LS	TRAFFIC CONTROL (STP 027-1(22))	641.10	-			
								BEGIN OPTION BB					
				900		900	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	30			
				900		900	LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	30			
				900		900	LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	30			
								END OPTION BB					

PROJECT NAME: FLETCHER
 PROJECT NUMBER: STP 027-1(22)
 FILE NAME: ...\\plotfiles\z11b064bdr_qty1.dgn PLOT DATE: 11/15/2012
 PROJECT LEADER: GAE DRAWN BY: STANTEC
 DESIGNED BY: ISM CHECKED BY: MCF
QUANTITY SHEET 1 SHEET 352 OF 387