

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES			
				ROADWAY	EROSION CONTROL	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS
								BEGIN OPTION CC					
				900		900	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	30	735	SY	SLIDE 1 STONE SLOPE REINFORCEMENT
				900		900	LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	30	635	SY	SLIDE 2 DRAINAGE (STONE FILL, TYPE 1)
				900		900	LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	30	58	SY	SLIDE 2 DRAINAGE (STONE FILL, TYPE 1)
								END OPTION CC			22	SY	ROUNDING
				2850		2850	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	18	1450	SY	TOTAL
				1800		1800	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	60			
				30		30	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	2			
				350		350	SF	PAVEMENT MARKING MASK	646.86	7			
				1450		1450	SY	GEOTEXTILE UNDER STONE FILL	649.31	22			
					190	190	SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	11			
				25		25	LB	SEED	651.15	EST.			
				200		200	LB	FERTILIZER	651.18	EST.			
				1		1	TON	AGRICULTURAL LIMESTONE	651.20	EST.			
				1		1	TON	HAY MULCH	651.25	EST.			
				20		20	CY	TOPSOIL	651.35	EST.			
					350	350	SY	TEMPORARY EROSION MATTING	653.20	4			
					12	12	CY	TEMPORARY STONE CHECK DAM, TYPE 1	653.25	1.4			
					120	120	CY	VEHICLE TRACKING PAD	653.35	-			
					660	660	LF	BARRIER FENCE	653.50	9			
					245	245	LF	PROJECT DEMARCATION FENCE	653.55	6			
				1		1	EACH	DELINEATOR WITH STEEL POST	676.10	-			
				1		1	EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40	-			
				180		180	CY	SPECIAL PROVISION (DRAINAGE AGGREGATE)	900.608	1			
				1		1	LS	SPECIAL PROVISION (TEMPORARY ROADWAY WIDENING) (SITE 1)	900.645	-			
				1		1	LS	SPECIAL PROVISION (TEMPORARY ROADWAY WIDENING) (SITE 2)	900.645	-			
				1460		1460	SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	10			
				15		15	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	1			
				470		470	TON	SPECIAL PROVISION (MATERIAL TRANSFER DEVICE)	900.680	5			
				10		10	TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	4.56			
				15		15	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	3			

PROJECT NAME: FLETCHER
PROJECT NUMBER: STP 027-1(22)
FILE NAME: ...\\plotfiles\z11b064bdr_qty2.dgn PLOT DATE: 11/15/2012
PROJECT LEADER: GAE DRAWN BY: STANTEC
DESIGNED BY: ISM CHECKED BY: MCF
QUANTITY SHEET 2 SHEET 353 OF 387