ITEM DETAIL SUMMARY SHEET 6

LOCATION			MISCELLANEOUS																REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	616.47 BIT. CONC. GUTTERS & TRAFF. ISL. TON	617.10 RELOCATE MAILBOX, SINGLE SUPP. EA	617.12 RELOCATE MAILBOX, MULTIPLE SUPP. EA	618.10 PORT. CEM. CONC. SIDEWALK, 5 INCH SY	618.30 DET. WARNING SURFACE SF	649.31 GEOTEXTILE UNDER STONE FILL SY	653.20 TEMPORARY EROSION MATTING SY	676.10 DELINEATOR WITH STEEL POST EA	676.12 REMOVAL OF EXIST. DELINEATOR EA								
VT ROUTE 116																			
HINESBURG																			
239+34		LT							6										INSTALL NEW VERTICAL GRANITE CURB FOR DI REHAB
239+98		RT				6	10												CONSTRUCT SIDEWALK RAMP, TYPE 1
240+16		RT				3	8												CONSTRUCT SIDEWALK RAMP, TYPE 1
240+33		LT				9	8												CONSTRUCT SIDEWALK RAMP, TYPE 1
241+25		LT				14	10												CONSTRUCT SIDEWALK RAMP, TYPE 6
250+94.7	251+07.2	LT							25	2	2								INSTALL ANCHOR @ STA. 250+94.7
251+25.0	251+37.5	RT							25	2	2								INSTALL ANCHOR @ STA. 251+25.0
260+27		LT				4	8												CONSTRUCT SIDEWALK RAMP, TYPE 2
260+39	260+53	RT							8										REMOVE & INSTALL CONCRETE CURB DURING WIDENING OF COMMERCE STREET SEE NEW CURB AND WIDENING DETAIL ON SHEET 18
260+97	261+27	RT							4										REMOVE & INSTALL CONCRETE CURB DURING WIDENING OF COMMERCE STREET SEE NEW CURB AND WIDENING DETAIL ON SHEET 18
260+98		RT				5	8												CONSTRUCT SIDEWALK RAMP, TYPE 2
264+82.5	266+09.0	RT							50	2	2								INSTALL ANCHORS @ STA. 264+84.0 AND 266+09.0. REFER TO DETAIL OF HD STEEL BEAM GUARDRAIL AT SMALL CULVERTS ON SHEET 18.
265+14.0	266+21.5	LT							50	2	2								INSTALL ANCHORS @ STA. 265+21.5 AND 266+21.5. REFER TO DETAIL OF HD STEEL BEAM GUARDRAIL AT SMALL CULVERTS ON SHEET 18.
288+30.0	290+67.5	LT						24	64	2	2								INSTALL ANCHORS @ STA. 288+30.0 AND 290+67.5. REPAIR SLOPE EROSION AT 288+77 & 289+24. SEE DETAIL ON SHEET 4.
288+42.5	290+08.0	RT							50	2	2								INSTALL ANCHORS @ STA. 288+42.5 AND 290+05.0
291+98.0	302+76.0	LT							50	2	2								INSTALL ANCHORS @ STA. 292+00.0 AND 302+75.0. REFER TO REDUCED POST SPACING DETAIL ON SHEET 18.
326+86.0	330+52.0	LT	0.3					65	91	2	2								INSTALL ANCHORS @ STA. 326+88.5 AND 330+51.0. INSTALL PERPENDICULAR BIT. GUTTER STA. 328+90, REFER TO DETAIL ON SHEET 18. REPAIR SLOPE EROSION AT 327+40, 327+72, 327+80 & 327+92 - 328+10. REFER TO DETAIL ON SHEET 4.
327+05.0	330+84.0	RT						12	57	2	2								INSTALL ANCHORS @ STA. 327+05.0 AND 330+80.0. STEEL BEAM GUARDRAIL 8' POST, GALVANIZED FROM STA. 328+55.0 TO 328+92.5. REPAIR SLOPE EROSION AT 329+19. REFER TO DETAIL ON SHEET 4.
337+92.5	339+08.0	LT							50	2	2								INSTALL ANCHORS @ STA. 337+92.5 AND 339+05.0
337+94.0	339+46.0	RT							50	2	2								INSTALL ANCHORS @ STA. 337+95.0 AND 339+45.0
343+46.5	346+46.0	LT							50	2	2								INSTALL ANCHORS @ STA. 343+47.0 AND 346+47.0
351+78.0	353+67.5	LT							50	2	2								INSTALL ANCHORS @ STA. 351+80.0 AND 353+67.5
SHEET 10 SUBTOTALS:			4.4	16	6	-	-	1200	5239	46	41								
SHEET 12 SUBTOTALS:			3.9	-	-	21	44	169	2643	36	36								
SHEET 14 SUBTOTALS:			0.3	-	-	41	52	101	680	26	26								
SUBTOTALS			8.6	16	6	62	96	1470	8562	108	103								
ROUNDING			1.4	-	-	3	4	30	38	2	2								
TOTALS			10	16	6	65	100	1500	8600	110	105								

ITEM DETAIL SUMMARY SHEET #6

PROJECT NAME: STARKSBORO-HINESBURG
PROJECT NUMBER: STP 2930(1)

FILE NAME: p10b266.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10b266idss06.i

PLOT DATE: 28-NOV-2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 14 OF 119