STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 07

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75	SQUARE STEEL (In) lb/ft 2.0	SQUARE STEEL (In) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD	TUBULAR STEEL Ø (In) FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0	TUBULAR STEEL Ø (In) lb/ft 3.5	TUBULAR STEEL Ø (In) lb/ft 4.0	TUBULAR STEEL Ø (In) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM BOOK	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
STARKSBORO																																				
316+80, RT	1160 0119 0600	1	6	10	0.42						1				X			X															VD-700			E-138
325+45, RT	BRIDGE 20 VT 116	1	6	8	0.33						1				X			X															VD-701			E-134
325+70, LT	BRIDGE 20 VT 116	1	6	8	0.33						1				X			X															VD-701			E-134
327+36, LT	1160 0119 0620	1	6	10	0.42						1				X			X															VD-700			E-138
337+92, RT	1160 0119 0640	1	6	10	0.42						1				X			X															VD-700			E-138
348+48, LT	1160 0119 0660	1	6	10	0.42						1				X			X															VD-700			E-138
352+17.60, LT	Starksboro / Hinesburg	1	72	10	5.00						2					X		X															VD-024		112	
	Addison Co / Chittenden Co	1	72	10	5.00																												VD-025		115	
	1160 0119 0668	1	6	10	0.42																												VD-700			E-138
	1160 0407 0000	1	6	10	0.42																												VD-700			E-138
HINESBURG 10+56, RT	1160 0407 0020	1	6	10	0.42						1				X			X															VD-700			E-138
14+64, LT	VT Rte 116	1	42	12	3.50																												D3-1		112	
	STOP 1160 0407 0028 B-B	1	30	30	6.25						1						X	X															R1-1	X		
		1	6	10	0.42																												VD-700			E-138
15+04, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															VR-017			E-141
15+35, LT	Tyler Bridge Rd	1	54	12	4.50						2					X		X															D3-1		112	
												FT	FT	FT	FT ~~74~~ 55.25	FT ~~82~~ 63.75	FT ~~16~~ 13.75		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 33.27	SF	EA.	SF				FT			FT ~~172~~ 132.75					LB			EA.	LB				EA.	EA.	LB					

"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #7

PROJECT NAME: STARKSBORO-HINESBURG
PROJECT NUMBER: STP 2930(1)

FILE NAME: p10b266.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10b266tss07.i

PLOT DATE: 28-NOV-2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 90 OF 119