

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
									ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
									20	20		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	EST				
									1	1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22					
									30	30		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST				
									500	500		HR	FLAGGERS	630.15	EST				
									1	1		LS	MOBILIZATION/DEMOBILIZATION	635.11					
									1	1		LS	TRAFFIC CONTROL	641.10					
									2134	2134		SF	TRAFFIC SIGNS, TYPE A	675.20	EST				
									4770	4770		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341					
									501	501		EACH	REMOVING SIGNS	675.50	EST				
									51	51		EACH	ERECTING SALVAGED SIGNS	675.60	EST				
									15	15		EACH	DELINEATOR WITH STEEL POST	676.10					
									18	18		EACH	SPECIAL PROVISION (SOIL BEARING SLIP BASE) (2 1/2")	900.620					

PROJECT NAME: WOODFORD - MARLBORO
 PROJECT NUMBER: STPG SIGN (35)
 FILE NAME: I0B336_TS.DGN
 PROJECT LEADER: A. GAMBLE
 DESIGNED BY: J. KELLY
 QUANTITY SHEET 1
 PLOT DATE: 17-APR-2012
 DRAWN BY: J. KELLY
 CHECKED BY: A. GAMBLE
 SHEET 3 OF 80