DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.0 (LB / FT) 7.6	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
WOODFORD EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	S4-4P	24	10								1															
		A	S4-3P	24	8	FYG		1.33																	REPLACE SIGNS. RETAIN POST, FLASHING BEACON AND WIRING.	X		
		A	R2-1	24	30			5.00																		X		
		A	S4-4P	24	10			1.67																		X		
EB	0.949	A	D1-1E	72	20								1		X													
		A	VD1-1	72	20			10.00								2		X									7	
EB	1.136	A	S5-2	30	24		END SCHOOL ZONE						1		X													
		A	R2-1	24	30			5.00								1		X								X	TRIM BRUSH	
		A	S5-2	24	30			5.00																		X		
EB	1.291	A	W2-2L	30	30		LEFT SIDE ROAD			1				X														
EB	1.397	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
EB	1.454	A	S3-1	36	36			9.00								2		X							INSTALL 300 FEET EAST OF EXISTING AND 10 FEET WEST OF POLE WITH CONDUIT.	X		
EB	1.495	A	R2-1	24	30								1		X													
		A	R2-1	24	30			5.00								1		X								X	TRIM BRUSH	
EB	2.228	A	W1-2R	30	30		RIGHT CURVE						1		X													
							SHEET TOTALS	42.00	0.00	1	0	0	6	0	0	6		90		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	310.4	0.0	28.0	0.0	0.0	61	0.0	0.0	52		780.0		0			0.0					

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WOODFORD EB SHEET 2

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **11** OF **80**