DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WOODFORD EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M3-2	24	12			2.00						X							RETAIN POST						RETAIN POST	E-136B
		A	M1-5	24	24			4.00																				E-136B
		A	VM-120	18	24		MOLLY STARK BYWAY			1																		
EB	4.139	B	W1-13	48	48		ROLLING TRUCK CURVE			1				X														
		B	VW-224P	66	18		1 MILE AHEAD			1																		
EB	4.208	A	VD-062B	72	16		BUSINESS SIGN			1				X														
EB	4.295	A	VD-062BC	74.75	16		BUSINESS SIGN			1				X														
		A	VD-062C	74.75	16		BUSINESS SIGN			1																		
EB	4.584	A	W1-2L	30	30		LEFT CURVE						1		X													
		A	W13-1	18	18		40 MPH ADVISORY						1															
EB	4.616	A	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT (SIGN MISSING)						1		X													
EB	4.691	A	W9-1	36	36		RIGHT LANE ENDS			1				X														
EB	4.748	A	W4-2R	36	36		RIGHT LANE MERGE SYMBOL			1				X														
EB	4.856 - 4.996	A/B		6	8		DELINEATORS - SEE TABLE ON SHEET 5									14						PAID EACH				INSTALL BACK TO BACK WHITE DELINEATORS FROM EAST END OF RAIL TO SKI AREA DRIVE.		ITEM 676.10	
EB	5.234	A	R2-1	24	30								1		X													
							SHEET TOTALS	6.00	0.00	8	0	0	4	0	0	0		0			0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT			EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	310.4	0.0	28.0	0.0	0.0	61	0.0	0.0	52		780.0			0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WOODFORD EB SHEET 6

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **15** OF **80**