DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WOODFORD WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W11-2	30	30		PEDESTRIAN						1															
WB	~~8.400~~ 8.413	F	R3-9cP	30	12		BEGIN	2.50								1		X								~~INSTALL 70 FEET WEST OF EXISTING NO PARKING ASSEMBLY AND AT EDGE OF DRIVEWAY.~~	INTALLED IN EXISTING LOCATION X	
		F	R8-3	24	24		R	4.00										USE OLD ANCHOR									X	
WB	8.367	F	D4-1	30	24		PARKING	5.00								1		X								~~INSTALL ON WESTERLY SIDE OF DRIVE FOR PARKING AREA.~~	MOVED EAST OF SIDE DRIVE X	
WB	8.322	F	R8-3A	24	24								1		X													
		F	R8-3	24	24		R	4.00								1		X									X	
WB	8.189	F	R8-3A	24	24								1		X													
		F	R8-3	24	24		R	4.00								1		X									X	
WB	8.120	F	R8-3A	24	24		NO PARKING SYMBOL						1		X													
		F	M4-6P	24	12		END						1															
EB	8.100	A	R3-9dP	30	12		END	2.50								1		X								INSTALL 100+/- FEET WEST OF EXISTING END NO PARKING ASSEMBLY. SHOULD BE DIRECTLY ACROSS FROM NEW BEGIN NO PARKING ASSEMBLY.	X	
		A	R8-3	24	24		R	4.00																			X	
WB	7.655	G	VR-023B	24	30		$500 FINE FOR THROWING TRASH			1				X														
WB	6.915	F	W1-4L	30	30		LEFT REVERSE CURVE						1		X													
		F	W13-1	18	18		40 MPH ADVISORY						1															
SIGN SUMMARY SHEET							SHEET TOTALS	26.00	0.00	1	0	0	7	0	0	5		75		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	260.8	0.0	9.0	4.0	4.0	60	0.0	0.0	48		720.0		0		0.0						

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**
FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WOODFORD WB SHEET 2
PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **22** OF **80**