DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WOODFORD WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	1.170	F	S1-1	36	36								~~1~~		X												T. BUCK REMOVED		
		F	S1-1	36	36	FYG	T. BUCK WILL INSTALL AT A LATER DATE	9.00*								2		X								• T. BUCK WILL INSTALL ONCE BRIDGE IS DONE, GIVEN TO LEE ABLE X		
		F	S4-3P	24	8	FYG	SCHOOL	1.33*																		X		
WB	1.126	F	S4-3P	24	8								1	X							RETAIN POST							
		F	R2-1	24	30								1															
		F	S4-4P	24	10								1															
		F	S4-3P	24	8	FYG		1.33																		REPLACE SIGNS. RETAIN POST, FLASHING BEACON AND WIRING.	X		
		F	R2-1	24	30		SCHOOL SPEED LIMIT 25 WHEN FLASHING	5.00																			X		
		F	S4-4P	24	10			1.67																			X		
WB	1.053	F	D1-1E	72	20		WOODFORD HOLLOW ELEM SCHOOL (RIGHT)						1		X														
WB	1.025	F	VD1-1	72	20		Woodford Hollow Elem. School →	10.00								2		X								INSTALL 150 FEET WEST OF EXISTING SCHOOL DESTINATION SIGN.		7	
WB	0.869	F	S5-2	30	24		END SCHOOL ZONE						1		X													
		F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL DIRECTLY ACROSS FROM EB SCHOOL FLASHING BEACON ASSEMBLY.	X		
		F	S5-2	24	30		END SCHOOL ZONE	5.00																			X		
WB	0.779	F	R2-1	24	30		SPEED LIMIT 40						1		X														
							SHEET TOTALS	38.33	0.00	0	0	0	~~7~~ 6	0	0	5		75		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	260.8	0.0	9.0	4.0	4.0	60	0.0	0.0	48		720.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WOODFORD WB SHEET 8

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **28** OF **80**