DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.0 (LB / FT) 7.6	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
SEARSBURG EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M1-5	24	24		VERMONT 9	4.00																					E-136B
EB	1.353	A	W7-4	78	40		RUNAWAY TRUCK RAMP 1 MILE			1				X															
EB	1.462	A	VW-092	30	30		UNSAFE TO PASS			1				X															
EB	1.580	A	W7-1	30	30		HILL SYMBOL (8%)			1				X															
		A	W7-3A	24	18		NEXT 2 MILES			1																			
EB	1.670	A	W2-2R	30	30		RIGHT SIDE ROAD			1				X															
EB	1.698	A	M2-1	21	15		JCT			1				X															
		A	M1-5	24	24		VERMONT ROUTE 8			1																			
EB	1.743	A	D1-1A	72	12		↑ WILMINGTON 7				1	1	1		X	2	SLIP	BASES	X							REINSTALL SIGNS ON NEW POSTS AND SLIP-BASES. SEE SHEET 2.		SLIP BASES	
		A	D1-1S	72	12		↑ SKI AREAS				1	1	1																
		A	D1-1A	72	12		↑ BRATTLEBORO 24				1	1	1																
		A	D1-1A	72	12		HEARTWELLVILLE 6 ---->						1																
		A	D1-1A	72	12		READSBORO 11 ---->				1	1	1													MOVE SIGN UP			
		A	D1-1A	72	12		STAMFORD 12 ---->				1	1	1													MOVE SIGN UP			
EB	1.812	A	M3-2	24	12		ROUTE MARKER ASSEMBLY				1	1	1		X	2			X							REINSTALL SIGNS AND FRAME ON NEW POSTS WITH SLIP-BASES. SEE SHEET 2.			
							SHEET TOTALS	4.00	0.00	7	6	6	7	0	0	4		60		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	130.8	0.0	29.0	18.0	18.0	41	0.0	0.0	28		420.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
SEARSBURG EB SHEET 2

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **31** OF **80**