DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SEARSBURG WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	5.518	F	R2-1	24	30								1	X							RETAIN POST					RETAIN FLANGED CHANNEL POST.			
		F	R2-1	24	30		SPEED LIMIT 50	5.00																			X		
WB	4.590	F	VW-005	30	30		BRIDGES FREEZE BEFORE ROAD						1		X											REMOVE FLAGS.			
		F	W8-13	36	36		BRIDGE ICES BEFORE ROAD	9.00								2		X									X		
		F	W7-3aP	24	18		NEXT 1 MILE	3.00																			X		
WB	4.490	G	VR-017	24	30								1	X							RETAIN POST					~~LIND LANE (TH-8)~~			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																				7	
WB	4.484	H	R1-1	30	30						I	I	I 1	X							RETAIN POST					LIND LANE (TH-8)	STREET SIGN ON TOP OF STOP SIGN INSTALLED 9-11		
		H	R1-1	30	30		STOP	6.25																			X		
WB	3.488	F	W2-1M	36	36		MODIFIED CROSSROADS						I 1		X												REMOVE OLD POSTS FOR ONE MISSING SIGN		
WB	3.446	F	W2-1	36	36			9.00								2		X								INSTALL ~~225~~ 100 FEET WEST OF EXISTING CROSSROADS SIGN.	X	PER JOE KELLY	
WB	3.390	F	D17-2	42	42		TRUCK LANE ¼ MILE	12.25								2		X								INSTALL ~~300~~ 600 FEET WEST OF NEW CROSSROADS SIGN.		PER JOE KELLY 6	
WB	3.362	G	VR-017	24	30		LEGAL LOAD 24K			1				X												SOMERSET RD (TH-4)			
WB	3.356	H	R1-1	30	30		STOP			1				X												SOMERSET RD (TH-4)			
WB	3.321	F	R2-1	24	30		SPEED LIMIT 50			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	49.50	0.00	3	0	0	~~7~~ 5	0	0	6		90		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	86.0	0.0	21.0	17.0	17.0	34	0.0	0.0	18		270.0		0	0.0							

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
SEARSBURG WB SHEET 1

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **37** OF **80**