DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	3.0 / 7.6	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	PROJECT SHEET #	STANDARD SHEET #
SEARSBURG WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M3-3	24	12						1	1	1																
		F	M1-5	30	24						1	1	1																
		F	M6-1	21	15						1	1	1																
		F	M3-4	24	12						1	1	1																
		F	M1-5	24	24						1	1	1																
		F	M6-3	21	15						1	1	1																
WB	1.824	F	W9-1R	30	30		RIGHT LANE ENDS						1		X														
WB	1.823	G	W1-7	48	24		DOUBLE HEADED ARROW			1				X															
WB	1.792	F	VD2-1	72	10								1		X														
		F	VD2-1	72	12			6.00								2		X								7	
		F	M3-4	24	12			2.00																	INSTALL ON LEFT POST.			E-136B
		F	M1-5	24	24			4.00																		INSTALL ON LEFT POST.			E-136B
		F	VM-120	18	24		MOLLY STARK BYWAY					1														RELOCATE SIGN FROM MP 1.760+/-. INSTALL ON LEFT POST.			
WB	1.760	F	M3-4	24	12		WEST						1		X														
		F	M1-5	24	24		VERMONT ROUTE 9 (MISSING)						1																
							SHEET TOTALS	12.00	0.00	1	6	7	10	0	0	2		30		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	86.0	0.0	21.0	17.0	17.0	34	0.0	0.0	18		270.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
SEARSBURG WB SHEET 4

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **40** OF **80**