| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS | | EXISTING SIGNS | | | | EXIST POST | | NUMBER OF NEW POSTS | SQUARE STEEL (IN) | | | TUBULAR STEEL Ø (IN) | | | | | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | "A" | "B" | RETAIN | SALVAGE FROM | SALVAGE TO | REMOVE | RETAIN | REMOVE | | 1.75 (LB / FT) | 2.00 (LB / FT) | 2.50 (LB / FT) | FOUNDATION | 3.0 (LB / FT) | 3.50 (LB / FT) | 4.00 (LB / FT) | 5.00 (LB / FT) | | | SHSM | PROJECT SHEET # | STANDARD SHEET # |
| | | | | | | | | | | | | | | | | | 1.88 | 2.42 | 3.35 | | 7.6 | 9.00 | 10.80 | 14.60 | | | | | |
| **SEARSBURG WB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | | F | VM-120 | 18 | 24 | | MOLLY STARK BYWAY | | | | 1 | | 1 | | | | | | | | | | | | | RELOCATE SIGN TO D-BOARD ASSEMBLY AT MP 1.792+/- | | | |
| WB | 1.752 | G | VR-017 | 24 | 30 | | LEGAL LOAD 24K | | | 1 | | | | X | | | | | | | | | | | | TOWN GARAGE RD (TH-7) | | | |
| WB | 1.745 | H | R1-1 | 30 | 30 | | STOP | | | 1 | | | | X | | | | | | | | | | | | TOWN GARAGE RD (TH-7) | | | |
| WB | 1.714 | F | W4-2R | 36 | 36 | | RIGHT LANE REDUCTION | | | 1 | | | | X | | | | | | | | | | | | | | | |
| WB | 1.679 | F | VW-054R | 30 | 30 | | HIDDEN DRIVE RIGHT | | | 1 | | | | X | | | | | | | | | | | | | | | |
| WB | 1.642 | F | VW-000 | 30 | 30 | | MOOSE CROSSING | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | F | W7-3A | 24 | 18 | | NEXT 2 MILES | | | 1 | | | | | | | | | | | | | | | | | | | |
| WB | 1.060 | F | | | | | (EMPTY POST) 0090 0212 0106 REMOVE | | | | | | 1 | | X | | | | | | | | | | | | REMOVE EMPTY POST. | | | |
| WB | 0.925 | F | VW-139 | 30 | 30 | | LIVESTOCK CROSSING (MISSING) | | | | | | 1 | | X | | | | | | | | | | | | SIGN IS NO LONGER WARRANTED. | | | |
| WB | 0.556 | F | W11-6H | 30 | 30 | | SNOWMOBILE | | | | | | 1 | | X | | | | | | | | | | | | SIGN IS NOT WARRANTED DUE TO ADEQUATE SSD. | | | |
| WB | 0.458 | F | M3-4 | 24 | 12 | | WEST | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | F | M1-5 | 24 | 24 | | VERMONT ROUTE 9 | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| SIGN SUMMARY SHEET | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| VERMONT AGENCY OF TRANSPORTATION | SHEET TOTALS | 0.00 | 0.00 | 8 | 1 | 0 | 4 | 0 | 0 | 0 | 0 | | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | |
| | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | | EA | LB | LB | LB | LB | | |
| | TOWN DIRECTIONAL TOTALS | 86.0 | 0.0 | 21.0 | 17.0 | 17.0 | 34 | 0.0 | 0.0 | 18 | 270.0 | | | | 0 | 0.0 | | | | | |

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**
FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SEARSBURG WB SHEET 5
SHEET **41** OF **80**