DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WILMINGTON EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.000	C	VD-024	60	7.5								1		X													
		C	VD-025	60	7.5								1															
		C	VD-024	72	10		Wilmington | Searsburg	5.00								2		X									4	
		C	VD-025	72	10		Windham Co | Bennington Co	5.00																			4	
		C	VD-700	6	10		0090 1322 0000	0.42																		INSTALL ON LH POST BELOW WILMINGTON			E-138
		C	VD-700	6	10		0090 0212 0554	0.42																		INSTALL ON RH POST BELOW SEARSBURG			E-138
EB	0.185	A	VD-123	36	36		511 TRAVEL INFO	9.00								2		X								INSTALL 200 FEET IN ADVANCE OF SIDE ROAD WARNING SIGN.		6	
EB	0.223	A	W2-2R	30	30								1		X													
		A	W2-2R	30	30			6.25								1		X									X	
EB	0.307	C	VR-017	24	30								1	X												WOODS RD (TH-31)		RETAIN POST	
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																		RETAIN EXISTING POST.		7	
EB	0.313	D	R1-1	30	30								1	X												WOODS RD (TH-31)		RETAIN POST	
		D	R1-1	30	30		STOP	6.25																		RETAIN EXISTING POST.	X		
EB	0.766	A	VD-062DBR	24	24		MOLLY STARK OBLISK			1				X														
EB	0.805	A	VD-062D	24	24		TRAVEL INFO			1				X														
							SHEET TOTALS	37.34	0.00	2	0	0	5	0	0	5		75		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	56.8	0.0	7.0	0.0	0.0	9	0.0	0.0	7		105.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WILMINGTON EB SHEET 1

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **42** OF **80**