DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WILMINGTON EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.984	A					PICNIC AREA RIGHT			1				X														
EB	1.000	C	VR-017	24	30		LEGAL LOAD 24K			1				X														
EB	1.006	D	R1-1	30	30		STOP			1				X														
EB	1.041	A	W11-2	30	30								1		X													
		A	W16-2	24	12		500 FEET						1															
		A	W11-2	30	30	FYG		6.25								1		X								X	
		A	W16-9P	24	12	FYG		2.00																				X	
EB	1.131	C	VR-017	24	30		LEGAL LOAD 24K			1				X														
EB	1.137	D	R1-1	30	30		STOP			1				X														
EB	1.144	A	W11-2	30	30								1		X													
		A	W16-7	24	12		(DOWN ARROW)						1															
		A	W11-2	30	30	FYG		6.25								1		X								X	
		A	W16-4P	30	24	FYG		5.00																				X	
				SKIP FROM MP 1.50+/- TO MARLBORO TOWN LINE DUE TO RECENT SIGN REPLACEMENTS																										
							SHEET TOTALS	19.50	0.00	5	0	0	4	0	0	2		30		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	56.8	0.0	7.0	0.0	0.0	9	0.0	0.0	7		105.0		0			0.0					

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336** PLOT DATE: **4/10/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
WILMINGTON EB SHEET 2 SHEET **43** OF **80**