DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MARLBORO EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	5.437	A	W1-8L	24	30		CHEVRON			1				X															
EB	5.454	A	S1-1	36	36		SCHOOL PENTAGON			1				X												RETAIN SIGN, POSTS AND FLASHING BEACONS.		RETAIN POSTS	
		A	W16-9	30	18		AHEAD						1																
		A	S4-3P	36	12	FYG	SCHOOL	3.00																		INSTALL BELOW EXISTING SCHOOL SYMBOL SIGN.	X		
EB	5.496	A	D1-1E	72	20								1	X														RETAIN POSTS	
		A	VD1-1	72	20		Marlboro Elem. School →	10.00																				7	
EB	5.762	A	VW-092	36	36								1	X														RETAIN POSTS	
		A	VW-092	36	36		UNSAFE TO PASS	9.00																				8	
EB	5.803	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
EB	6.009	A	W1-8L	18	24		CHEVRON						1		X														
EB	6.053	A	R2-1	24	30		SPEED LIMIT 50						1		X														
EB	6.056	A	W1-8L	18	24		CHEVRON						1																
		A	W1-6L	48	24	FY	←	8.00								2		X									X		
EB	6.084	A	W1-8L	18	24		CHEVRON						1		X														
EB	6.324	A	VW-205	36	36		WATCH FOR TURNING VEHICLES						1		X														
							SHEET TOTALS	30.00	0.00	2	0	0	9 ~~8~~	0	0	2		30		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	634.4	0.0	28.0	1.0	1.0	127	0.0	0.0	88		1320.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: WOODFORD-MARLBORO
PROJECT NUMBER: STPG SIGN(35)

FILE NAME: 10B336
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
MARLBORO EB SHEET 13

PLOT DATE: 4/10/2012
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE
SHEET 58 OF 80