DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.0 7.6	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MARLBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W13-1P	18	18		40 MPH ADVISORY						1															
WB	7.049	F	R2-1	24	30		SPEED LIMIT 50			1				X														
WB	7.003	F	W9-1R	36	36			9.00								2		X								INSTALL ON EASTERLY SIDE OF EXISTING CHEVRON.	X		
WB	7.002	E	W1-8R	18	24								1		X													
		E	W1-8R	24	30			5.00								1		X									X		
WB	6.977	F	W1-8L	18	24		CHEVRON						1		X											CURRENT CHEVRONS ARE ON AN ADJUSTABLE BRACKET.			
		E	W1-8R	18	24								1															
		E	W1-8R	24	30			5.00								1		X									X		
WB	6.954	F	W1-8L	18	24		CHEVRON						1		X											CURRENT CHEVRONS ARE ON AN ADJUSTABLE BRACKET.			
		E	W1-8R	18	24								1															
		E	W1-8R	24	30			5.00								1		X									X		
WB	6.941	F	W4-2R	36	36								1	X														
		F	W4-2R	36	36			9.00																			X		
WB	6.823	F	VR-186	24	30		TRUCK LANE ENDS						1		X														
WB	6.776	F	W1-10L	30	30		LEFT CURVE WITH SIDE ROAD RIGHT						1		X														
							SHEET TOTALS	33.00 SF	0.00 SF	1 EA	0 EA	0 EA	9 EA	0 EA	0 EA	5 EA		75 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	607.1 SF	0.0 SF	23.0 EA	1.0 EA	1.0 EA	117 EA	0.0 EA	0.0 EA	70 EA		1050.0 FT		0 EA	0.0 LB								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
MARLBORO WB SHEET 4

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **67** OF **80**