DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MARLBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W16-9	30	18		AHEAD						1															
		F	S4-3P	36	12	FYG	SCHOOL	3.00																		INSTALL BELOW SCHOOL SYMBOL SIGN.	X		
WB	5.760	F	W4-2R	36	36								1	X							RETAIN POST							
		F	W4-2R	36	36			9.00																			X		
WB	5.708	F	D1-1E	72	20								1	X							RETAIN POST							
		F	VD1-1	72	20		Marlboro Elem. School	10.00																				7	
WB	5.617	F	VR-186	24	30		TRUCK LANE ENDS						1		X													
WB	5.599	F	VD-062B	72	16		BUSINESS SIGN			1				X														
WB	5.496	F	W1-10R	30	30								1		X											SIGN ASSEMBLY IS MISSING.			
		F	W13-1	24	24		35 MPH ADVISORY						1															
		F	W1-10R	36	36	FY		9.00								2		X									X		
		F	W16-8P	24	8	FY	South Rd	1.33																				8	
WB	5.438	F	D1-1A	72	10								1	X	~~X~~						RETAIN POST					CONTRACTOR THINKS IT'S A GOOD IDEA TO RETAIN POSTS- NEW ELECTRICAL.			
		F	VD1-1A	72	12		Marlboro 1	6.00								~~2~~		~~X~~									6	
WB	5.364	F	M3-4	24	12								1	X														
SIGN SUMMARY SHEET							SHEET TOTALS	38.33	0.00	1	0	0	8	0	0	4		60		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	607.1	0.0	23.0	1.0	1.0	117	0.0	0.0	70		1050.0		0		0.0						

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
MARLBORO WB SHEET 7

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **70** OF **80**