DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MARLBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M1-5	24	24								1																
		F	M3-4	24	12			2.00																				E-136B
		F	M1-5	24	24			4.00																				E-136B
WB	5.328	F	R2-1	24	30		SPEED LIMIT 50						1		X														
WB	5.252	F	R2-1	24	30			5.00								1		X								INSTALL ~~400~~ 600' FEET WEST OF EXISTING SPEED LIMIT 50 SIGN ASSEMBLY.	X	CHANGE LOCATION	
WB	4.803	G	VR-017	24	30								1	POST ~~X~~	BENT X												CHURCH HOLLOW RD (TH-20)			
		G	VR-017	24	30			5.00																				7	
WB	4.794	H	R1-1	30	30								1	X													CHURCH HOLLOW RD (TH-20)			
		H	R1-1	30	30			6.25																			X		
WB	4.775	F	M3-4	24	12								1	X															
		F	M1-5	24	24								1																
		F	M3-4	24	12			2.00																				E-136B
		F	M1-5	24	24			4.00																				E-136B
		F	VM-120	18	24		BYWAY SIGN MISSING			~~1~~																		BYWAY SIGN MISSING	
WB	4.620	F	D17-2	42	42			12.25								2		X								INSTALL 820 FEET WEST OF WB ROUTE MARKER ASSEMBLY.		6	
							SHEET TOTALS	40.50	0.00	1	0	0	6	0	0	3		45		0	0.0	0.0	0.0	0.0			
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB			
							TOWN DIRECTIONAL TOTALS	607.1	0.0	23.0	1.0	1.0	117	0.0	0.0	70		1050.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
MARLBORO WB SHEET 8

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **71** OF **80**