DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MARLBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M1-5	24	24		VERMONT ROUTE 9						1																
WB	2.547	F	R2-1	24	30		SPEED LIMIT 50						1		X														
		F	VW-133R	30	30		HIDDEN DRIVES RIGHT	6.25								1		X										TRIM BRUSH 8	
WB	2.091	A	D17-2	42	42		TRUCK LANE ¼ MILE	12.25								2		X									INSTALL 525 FEET EAST OF EXISTING LEFT CURVE SIGN ASSEMBLY.		6	
WB	1.992	F	W1-2L	30	30								1	X															
		F	W1-2L	30	30			6.25																				X	
WB	1.964	F	R4-6	24	30		TRUCK LANE 500 FEET						1		X														
WB	1.905	E	W1-8R	24	30	FY		5.00								1		X									INSTALL 20 FEET EAST OF CLOSEST EDGE OF HUGHS RD.	X		
WB	1.900	G	VR-017	24	30								1	X													HUGHS RD (TH-31)			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																					7	
WB	1.893	H	R1-1	30	30		0090 1311 0191						1	X													HUGHS RD (TH-31)			
		H	R1-1	30	30		STOP	6.25																				X	
WB	1.887	F	W1-8L	24	30		CHEVRON			1				X															
WB	1.887	E	W1-8R	24	30		CHEVRON			1				X															
WB	1.860	F	W1-8L	24	30		CHEVRON			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	41.00	0.00	3	0	0	6	0	0	4		60		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	607.1	0.0	23.0	1.0	1.0	117	0.0	0.0	70		1050.0		0		0.0						

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
MARLBORO WB SHEET 12

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **75** OF **80**