DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.0 (LB / FT) 7.6	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
MARLBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	1.860	E	W1-8R	24	30		CHEVRON			1				X														
WB	1.846	F	R4-3	36	48								1		X													
		F	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT	5.00								1		X									X		
WB	1.844	E	W1-8R	24	30		CHEVRON			1		I		X												MISSING- USE A SALVAGED ONE.		
WB	1.823	F	W1-8L	24	30		CHEVRON			1				X														
WB	1.823	E	W1-8R	24	30		CHEVRON			1				X														
WB	1.799	F	W1-8L	24	30		CHEVRON			1				X														
WB	1.799	E	W1-8R	24	30		CHEVRON			1				X														
WB	1.776	F	W1-8L	24	30								1	X												RETAIN POST		
		F	W1-8L	24	30	FY		5.00																			X	
WB	1.776	E	W1-8R	24	30		CHEVRON			1				X														
WB	1.752	F	W1-8L	24	30								1	X												RETAIN POST		
		F	W1-8L	24	30	FY		5.00																			X	
WB	1.752	E	W1-8R	24	30					~~1~~ I			~~1~~	X												RETAIN ALL		
		E	W1-8R	24	30	FY		~~5.00~~																			RETAIN X	
							SHEET TOTALS	~~15.00~~ 20.00 SF	0.00 SF	~~8~~ 7 EA	0 EA	~~1~~ 0 EA	~~3~~ 4 EA	0 EA	0 EA	1 EA	15 FT			0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	607.1	0.0	23.0	1.0	1.0	117	0.0	0.0	70	1050.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
MARLBORO WB SHEET 13

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **76** OF **80**