DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.0 (LB / FT) 7.6	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MARLBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	1.688	F	R2-1	24	30								1	X							RETAIN POST							
		F	R2-1	24	30		SPEED LIMIT 50	5.00								1		X									X		
WB	1.508	F	R4-3	36	48								1		X													
		F	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT	5.00								1		X									X		
WB	1.305	F	W9-1R	36	36	FY	RIGHT LANE ENDS	9.00								2		X									INSTALL 300 FEET EAST OF LANE MERGE SYMBOL SIGN.	X	MOVED CLOSER TO ROAD TO SEE BY POLE BETTER	
WB	1.248	F	W4-2R	36	36								1	X							RETAIN POST							
		F	W4-2R	36	36	FY		9.00																			X		
WB	1.203	F	W1-5L	30	30		WINDING ROAD LEFT 0140 1416 0000						1		X												CUT POST OFF ABOVE MILE MARKER		
WB	1.165	F	VD-062BRN	72	16		BUSINESS SIGN			1				X															
WB	1.128	F	VR-186	36	48		TRUCK LANE ENDS						1		X														
WB	1.086	G	VR-017	24	24		LEGAL LOAD 24,000 LBS						1		X												OLD HOGBACK RD. (TH-33)		
WB	1.078	H	R1-1	24	24		STOP MISSING						~~1~~		X												OLD HOGBACK RD. (TH-33)	STOP SIGN AND POST MISSING	
WB	1.057	F	M3-4	24	12		WEST						1		X														
		F	M1-5	24	24		VERMONT ROUTE 9						1																
WB	1.002	F	R2-1	24	30		SPEED LIMIT 50						1		X														
							SHEET TOTALS	28.00	0.00	1	0	0	~~10~~ 9	0	0	4		60		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	607.1	0.0	23.0	1.0	1.0	117	0.0	0.0	70		1050.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **WOODFORD-MARLBORO**
PROJECT NUMBER: **STPG SIGN(35)**

FILE NAME: **10B336**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
MARLBORO WB SHEET 14

PLOT DATE: **4/10/2012**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **77** OF **80**