TOWN TOTAL SIGN SUMMARY SHEET

WOODFORD - MARLBORO STPG SIGN(35)

Townname-Route	County	Town Mileage	NEW SIGNS (SF)		EXISTING SIGNS (EA)				EXIST POST (EA)		NUMBER OF NEW POSTS (EA)				SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				
											1.75"	2"	2.5"		1.75	2.00	2.50		3.00	3.50	4.00	5.00
											(LB / FT)				(LB / FT)				(LB / FT)			
			TYPE A	TYPE B	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE	1.88	2.42	3.35	TOTAL POSTS	1.88	2.42	3.35	FOUNDATION	7.60	9.00	10.80	14.60
Woodford VT-9 EB	Bennington	9.575	310.4	0	28	0	0	61	0	0	0	52	0	52	0	780	0					
Woodford VT-9 WB	Bennington	9.575	260.8	0	9	4	4	60	0	0	0	48	0	48	0	720	0					
Searsburg VT-9 EB	Bennington	5.538	130.8	0	29	18	18	41	0	0	0	22	6	28	0	330	90					
Searsburg VT-9 WB	Bennington	5.538	86.0	0	21	17	17	34	0	0	0	14	4	18	0	210	60					
Wilmington VT-9 EB	Windham	7.160	56.8	0	7	0	0	9	0	0	0	7	0	7	0	105	0					
Wilmington VT-9 WB	Windham	7.160	47.8	0	3	0	0	11	0	0	0	7	0	7	0	105	0					
Marlboro VT-9 EB	Windham	8.304	634.4	0	28	1	1	127	0	0	0	84	4	88	0	1260	60					
Marlboro VT-9 WB	Windham	8.304	607.1	0	23	1	1	117	0	0	0	66	4	70	0	990	60					
				Sub-Total		41	41	460						**Sub-Total**	0	4500	270					
Estimated Salvaged Street Name Signs to be erected onto new posts =							5															
Estimated Salvaged Mile Markers to be erected onto new posts =							5															
Salvaged From signs to be added to Remove total =								41														
		TOTAL =	2134	0	148	41	51	501	0	0	0	300	18	318	4770			0	0	0	0	0

PROJECT NAME:	WOODFORD - MARLBORO
PROJECT NUMBER:	STPG SIGN (35)
FILE NAME: 10B336_TS.DGN	PLOT DATE: 10-APR-2012
PROJECT LEADER: A. GAMBLE	DRAWN BY: J. KELLY
DESIGNED BY: J. KELLY	CHECKED BY: A. GAMBLE
TOWN TOTAL SIGN SUMMARY SHEET	SHEET 80 OF 80