



SOIL CLASSIFICATION
 WASHINGTON
 ADAMS LOAMY FINE SAND
 3-8% SLOPES
 "K FACTOR" 0.17
 CLASSIFIED SLIGHTLY ERODIBLE

NOTES

1. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH DISTURBANCE.
2. THESE PLANS SHOW A CONCEPTUAL EROSION CONTROL PLAN, THE CONTRACTOR SHALL SUBMIT A TEMPORARY EROSION CONTROL PLAN FOR APPROVAL. PAYMENT FOR DEVELOPMENT AND MODIFICATIONS TO THE EPSC SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 652.10.
3. TEMPORARY EROSION CONTROL MEASURES ARE CONCEPTUALLY SHOWN. THE CONTRACTOR MAY RELOCATE TEMPORARY MEASURES TO IMPROVE EROSION CONTROL WITH APPROVAL OF THE ENGINEER AND ON SITE COORDINATOR.
4. SILT FENCE SHALL NOT BE INSTALLED ACROSS CONTOURS.
5. THE CONTRACTOR SHALL USE OTHER TEMPORARY EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS DIRECTED BY THE ENGINEER AND ON SITE COORDINATOR.
6. REFER TO TEMPORARY EROSION CONTROL DETAIL SHEETS FOR ADDITIONAL DETAILS.
7. WHERE LEDGE IS EXPOSED, GRAVEL BAGS MAY BE USED INSTEAD OF FILTER CURTAIN. PAYMENT FOR GRAVEL BAGS WILL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 649.61 "GEOTEXTILE FOR FILTER CURTAIN".
8. ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED. SEE SEEDING FORMULA AND SEEDING NOTES FOR TURF REESTABLISHMENT REQUIREMENTS.
9. MONITORING AND MAINTAINING THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE PER ITEM 652.20, MONITORING EPSC PLAN AND ITEM 652.30, MAINTENANCE OF EPSC PLAN.

LEGEND

	CHECK DAM
	TURBIDITY CURTAIN
	SILT FENCE
	LIMITS OF SOIL DISTURBANCE
	PERMANENT EROSION MATTING
	PROJECT DEMARCATION FENCE
	STABILIZED CONSTRUCTION ENTRANCE
	RIPARIAN BUFFER ZONE
	HABITAT AREA
	ORDINARY HIGH WATER

20 0 20
 SCALE: 1" = 20'-0"



PROJECT NAME: WARREN
 PROJECT NUMBER: BRF 013-4(32)
 FILE NAME: z10b424bdr_ero.dgn PLOT DATE: 03-OCT-2013
 PROJECT LEADER: R. YOUNG DRAWN BY: P.Dustin
 DESIGNED BY: J. SANTACRUZE CHECKED BY: T. KENDRICK
 EPSC CONSTRUCTION SITE PLAN SHEET 39 OF 42