QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		TRAINING	FULL CE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				50	50	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	-
				18	18	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
				3606	3606	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
				1100	1100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
				4700	4700	HR	FLAGGERS	630.15	EST.
			1		1	LS	FIELD OFFICE, ENGINEERS	631.10	-
			1		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			3000		3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
		520			520	HR	EMPLOYEE TRAINEESHIP	634.10	-
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
				1	1	LS	TRAFFIC CONTROL	641.10	-
							BEGIN OPTION AA		
				69000	69000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1325
				69000	69000	LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	1325
				69000	69000	LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	1325
							END OPTION AA		
							BEGIN OPTION BB		
				65000	65000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	531
				65000	65000	LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	531
				65000	65000	LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	531
							END OPTION BB		
							BEGIN OPTION CC		
				115	115	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	2
				115	115	LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	2
				115	115	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	2
							END OPTION CC		
							BEGIN OPTION DD		
				29	29	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
				29	29	EA	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-
				29	29	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-
							END OPTION DD		
				340000	340000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	1624
				324000	324000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	1655
				570	570	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	5
				145	145	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
				3400	3400	EA	LINE STRIPING TARGETS	646.76	96

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: MONTGOMERY-WESTFIELD
PROJECT NUMBER: STP 2906(I)

FILE NAME: p10C190.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C190_12.1

PLOT DATE: 9/5/12
DRAWN BY: SJL
CHECKED BY: CDL
SHEET 12 OF 178