# QUANTITY SHEET 3

**STATE OF VERMONT**
**AGENCY OF TRANSPORTATION**

SUMMARY OF ESTIMATED QUANTITIES

| | | TRAINING | FULL CE | ROADWAY | QUANTITIES GRAND TOTAL | UNIT | ITEMS | ITEM NO. | ROUNDING |
|---|---|---|---|---|---|---|---|---|---|
| | | | | 16200 | 16200 | SY | GEOTEXTILE UNDER STONE FILL | 649.31 | 204.1 |
| | | | | 3700 | 3700 | SY | GEOTEXTILE FOR SILT FENCE | 649.51 | 48 |
| | | | | 330 | 330 | LB | SEED | 651.15 | EST |
| | | | | 1420 | 1420 | LB | FERTILIZER | 651.18 | EST |
| | | | | 6 | 6 | TON | AGRICULTURAL LIMESTONE | 651.20 | EST |
| | | | | 5 | 5 | TON | HAY MULCH | 651.25 | EST |
| | | | | 210 | 210 | CY | TOPSOIL | 651.35 | 4.3 |
| | | | | 5950 | 5950 | SY | GRUBBING MATERIAL | 651.40 | 48.8 |
| | | | | 11800 | 11800 | SY | TEMPORARY EROSION MATTING | 653.20 | 142.1 |
| | | | | 8620 | 8620 | LF | BARRIER FENCE | 653.50 | 1 |
| | | | | 8620 | 8620 | LF | EROSION LOG | 653.60 | 1 |
| | | | | 530 | 530 | SF | TRAFFIC SIGNS, TYPE A | 675.20 | 8.88 |
| | | | | 293 | 293 | LB | TUBULAR STEEL SIGN POST | 675.33 | - |
| | | | | 1660 | 1660 | LF | SQUARE TUBE SIGN POSTS AND ANCHOR | 675.341 | - |
| | | | | 2 | 2 | EA | FOUNDATION FOR TUBULAR STEEL POST | 675.43 | - |
| | | | | 129 | 129 | EA | REMOVING SIGNS | 675.50 | - |
| | | | | 18 | 18 | EA | DELINEATOR WITH STEEL POST | 676.10 | - |
| | | | | 18 | 18 | EA | REMOVAL OF EXISTING DELINEATOR | 676.12 | - |
| | | | | 1 | 1 | LU | PRICE ADJUSTMENT, FUEL (N.A.B.I.) | 690.50 | - |
| | | | | 108000 | 108000 | SY | SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT) | 900.675 | 1237 |
| | | | | 2100 | 2100 | SY | SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES) | 900.675 | 86.8 |
| | | | | 108000 | 108000 | SY | SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT) | 900.675 | 1237 |
| | | | | 1625 | 1625 | TON | SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION) | 900.680 | 24 |
| | | | | 260 | 260 | TON | SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING) | 900.680 | 20 |
| | | | | 34500 | 34500 | TON | SPECIAL PROVISION (MATERIAL TRANSFER DEVICE) | 900.680 | 169.7 |
| | | | | 1075 | 1075 | CWT | SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H) | 900.683 | EST. |
| | | | | 1350 | 1350 | CWT | SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT) | 900.683 | 4.8 |

DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|
| | | GEOTEXTILE UNDER STONE FILL |
| 9267.9 | SY | ITEM DETAIL SUMMARY SHEET 6 |
| 6728 | SY | DITCH CLEANING DETAIL SHEET |
| 204.1 | SY | ROUNDING |
| 16200 | SY | TOTAL |
| | | |
| | | TEMPORARY EROSION MATTING |
| 9717.9 | SY | ITEM DETAIL SUMMARY SHEET 6 |
| 1940 | SY | DITCH CLEANING DETAIL SHEET |
| 142.1 | SY | ROUNDING |
| 11800 | SY | TOTAL |

DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

PROJECT NAME: MONTGOMERY-WESTFIELD
PROJECT NUMBER: STP 2906(I)

FILE NAME: p10C190.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C190_13.1

PLOT DATE: 9/5/12
DRAWN BY: SJL
CHECKED BY: CDL
SHEET 13 OF 178