

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

ITEM DETAIL SUMMARY SHEET 6

BEGIN STATION	END STATION	POS.	203.30 EARTH BORROW CY	204.20 TRENCH EXCAV. OF EARTH CY	204.22 TRENCH EXCAV. OF EARTH, EXP. (N.A.B.I.) CY	204.30 CRAN. BACKFILL FOR STRUCTURES CY	402.12 AGG. SHOULD. TON	601.0010 15" CSP .064 (2-2/3 X 1/2) LF	601.0015 18" CSP .064 (2-2/3 X 1/2) LF	604.412 REHAB. D.I. CLASS I EACH	613.10 STONE FILL, TYPE I CY	619.17 YIELDING MARKER POSTS EACH	621.20 STEEL BEAM G.R. GALV LF	621.205 STEEL BEAM G.R. GALV W/8FT POSTS LF	621.207 STEEL BEAM G.R. GALV/NEST W/8 FT POSTS LF	621.60 ANCHOR FOR S.B. GUARDRAIL EACH	621.80 REMOVE & DISP. OF G.R. LF	649.31 GEOT. UNDER STONE FILL SY	651.35 TOPSOIL CY	651.40 GRUBBING MATERIAL SY	653.20 TEMP. EROSION MATTING SY	676.10 DELINE. WITH STEEL POSTS EACH	676.12 REMOVAL OF EXIST. DELINE. EACH	REMARKS
A 121+20	A 122+40	RT									19							83.6		37	83.6			PLACE STONE FILL ON SLOPES GREATER THAN 1:2 FOR SLOPE STABILIZATION
A 131+60	A 132+50	RT									27.8							103.4		68.4	103.4			PLACE STONE FILL ON SLOPES GREATER THAN 1:2 FOR SLOPE STABILIZATION
SUBTOTAL THIS SHEET			-	-	-	-	-	-	-	46.8	-	-	-	-	-	-	-	187	-	105.4	187	-	-	
SUBTOTAL SHEET 1			-	2	1	2	417.2	7.5	-	2	534.3	65	-	-	-	-	-	2033.4	68.4	1299.1	2033.4	-	-	
SUBTOTAL SHEET 2			50	2	-	2	-	4	3	-	349.1	-	554	277	-	4	831	1312.5	20	849.2	1412.5	4	4	
SUBTOTAL SHEET 3			50	-	-	-	284.5	-	-	-	494.9	56	229	204	-	4	425	1831.6	67.3	1228.1	1931.6	4	4	
SUBTOTAL SHEET 4			100	-	-	-	-	-	-	563.4	-	227	1839	50	8	2100	1978.7	40	1271.2	2178.7	8	8		
SUBTOTAL SHEET 5			25	-	-	-	-	-	-	505.9	-	254	-	-	2	250	1924.7	10	1148.2	1974.7	2	2		
ROUNDING			-	-	-	-	8.3	2.5	1	-	-	-	11	5	-	-	-	-	4.3	48.8	-	-	-	
TOTAL			225	4	1	4	710	14	4	2	2494.4	121	1275	2325	50	18	3606	9267.9	210	5950	9717.9	18	18	

**ITEM
DETAIL
SUMMARY
SHEET 6**

PROJECT NAME: MONTGOMERY-WESTFIELD

PROJECT NUMBER: STP 2906(I)

FILE NAME: pi0ci90.dgn

PROJECT LEADER: CDL

DESIGNED BY: SJL

PLOT FILE: pi0ci90_18B.1

PLOT DATE: 9/5/12

DRAWN BY: JBG

CHECKED BY: CDL

SHEET 18B OF 178