STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) lb/ft FOUND-ATION	3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. 0+53 LT MONTGOMERY	Montgomery 2	1	72	12	6.00						2												X	X								VD1-1A GREEN ON WHITE		98B	
	Jay Peak Jul. Aug. 8 11	1	72	12	6.00																											VD1-1A GREEN ON WHITE		98B	
	NORTH EAST	1 1	24 24	12 12	2.00 2.00																										*2B	M3-1 GREEN ON WHITE SIGN FRAME REQUIRED M3-2 GREEN ON WHITE	SHSM SHSM		
	VERMONT 118 VERMONT 242	1 1	30 30	24 24	5.00 5.00																											M1-5 GREEN ON WHITE M1-5 GREEN ON WHITE			E-136B E-136B
		1 1	21 21	15 15	2.19 2.19																											M6-2L GREEN ON WHITE M6-2R GREEN ON WHITE	SHSM SHSM		
STA. 0+54 RT MONTGOMERY	STOP	1	30	30	6.25						1					X		X														R1-1	SHSM		
STA. 0+59 LT MONTGOMERY	STOP	1	30	30	6.25						1					X		X														R1-1	SHSM		
																																			SEH 2-24-14
												LF	LF	LF	LF	LF 30	LF		EA.	LB	LB	LB		LB 293	LB	LB	LB								
		TOTALS	SF 42.88	SF	EA. -	SF						LF			LF 30					LB			EA. 2	LB 293				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 1

PROJECT NAME: MONTGOMERY-WESTFIELD
PROJECT NUMBER: STP 2906(1)

FILE NAME: p10C190.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C190_82.1

PLOT DATE: 9/5/12
DRAWN BY: SJL
CHECKED BY: CDL
SHEET 82 OF 178