STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 5

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS | | | NEW & SALVAGED SIGNS | | | | EXIST POST | | NEW SIGN POSTS | | | | | | | | | | | | | | | | | REMARKS | SIGN DETAIL | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | EA | WIDTH (in) | HEIGHT (in) | "A" | "B" | SALV SIGN | SALV TIS | RETAIN | SALVAGE | NO. OF POSTS | FLANGED CHANNEL lb/ft | | | SQUARE STEEL (in) lb/ft | | | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft | | | FOUNDATION | TUBULAR STEEL Ø (in) lb/ft | | | | W-SHAPE STEEL FTG. SIZE | | WEIGHT | POST SIZE | SIGN FRAMED REQUIRED | SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK | DETAIL IN SHSM | DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | 1.12 | 2.0 | 3.0 | 1.75 | 2.0 | 2.5 | | | 3.0 | 4.0 | 4.0 MOD | | 3.0 | 3.5 | 4.0 | 5.0 | 24" | 30" | | | | | | | |
| | | | | | | | | | | | | | | | 1.88 | 2.42 | 3.35 | | | 1.3 | 1.7 | 1.7 | | 7.6 | 9.0 | 10.8 | 14.6 | | | | | | | | | |
| STA. 24+23 RT MONTGOMERY | SPEED LIMIT 40 | 1 | 24 | 30 | 5.00 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | R2-1 | SHSM | | |
| STA. 26+21LT MONTGOMERY | | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | WI-2L | SHSM | | |
| STA. 27+90 LT MONTGOMERY | SPEED LIMIT 30 | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | X | | X | | | | | | | | | | | | | | | W3-5 | SHSM | | |
| STA. 29+77 LT MONTGOMERY | | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | X | | X | | | | | | | | | | | | | | | S3-1 FLUORESCENT YELLOW-GREEN WITH TYPE IX SHEETING | SHSM | | |
| STA. 31+68 RT MONTGOMERY | 2420 0610 0060 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | X | | | X | | | | | | | | | | | | | | | VD-700 | | | E-138 |
| STA. 33+04 LT MONTGOMERY | THIS ~~THIS~~ Sheldon Farm Rd | 1 | 60 | 12 | 5.00 | | | | | | 2 | | | | | X | | X | | | | | | | | | | | | | | | D3-1 | | 98A | |
| STA. 33+06 LT MONTGOMERY | STOP | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | RI-1 | SHSM | | |
| | 2420 0610 0063 | 1 | 6 | 10 | 0.42 | | | | | | | | | | | | | | | | | | | | | | | | | | | | VD-700 | | | E-138 |
| STA. 33+32 LT MONTGOMERY | DEAD END | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | WI4-1 | SHSM | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | SEH 2-24-14 |
| | | | | | | | | | | | | LF | LF | LF | LF 8 | LF 150 | LF | | EA. | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| | | | | | | | | | | | | | | | 158 | | | | | | | | | | | | | | | | | | | | | |
| TOTALS | | SF 47.59 | SF | EA. - | SF | | | | | | | LF | | | LF | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

**TRAFFIC SIGN SUMMARY SHEET 5**

PROJECT NAME: MONTGOMERY-WESTFIELD
PROJECT NUMBER: STP 2906(1)

FILE NAME: p10C190.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C190_86.1

PLOT DATE: 9/5/12
DRAWN BY: SJL
CHECKED BY: CDL
SHEET 86 OF 178