STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) lb/ft FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. A 137+86 RT WESTFIELD		1	30	30	6.25						1					X		X															W7-1b	SHSM		
		1	21	15	2.19																											W7-2b	SHSM		
STA. 45+40, RT MONTGOMERY	BRIDGE 1 VT 242	1	6	8	0.33						1				X			X																		
STA. 45+90, LT MONTGOMERY	BRIDGE 1 VT 242	1	6	8	0.33						1				X			X																		
STA. 83+52, RT MONTGOMERY	BRIDGE 2 VT 242	1	6	8	0.33						1				X			X																		
STA. 84+37, LT MONTGOMERY	BRIDGE 2 VT 242	1	6	8	0.33						1				X			X																		
STA. 120+78, RT MONTGOMERY	THI9 AMIDON RD	1	42	12	3.50																											MOUNTED ON STOP SIGN			
	TSSS 1 TOTAL TSSS 2 TOTAL TSSS 3 TOTAL TSSS 4 TOTAL TSSS 5 TOTAL TSSS 6 TOTAL TSSS 7 TOTAL TSSS 8 TOTAL TSSS 9 TOTAL TSSS 10 TOTAL TSSS 11 TOTAL TSSS 12 TOTAL TSSS 13 TOTAL TSSS 14 TOTAL TSSS 15 TOTAL TSSS 16 TOTAL				42.88 42.00 38.61 50.67 47.59 35.26 29.26 32.19 40.10 33.00 23.09 37.60 13.20 9.03 38.20 8.44										8 8 24 24 24 24 16 24 48 56 24	30 105 90 165 150 90 90 90 90 150 75 90 30 15 105 15									2	293									SEH 2-25-14
	SUBTOTAL				521.12							LF	LF	LF	LF	LF	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."	ROUNDING				8.88										280	1380								293											
	TOTALS				SF 530	SF	EA. -	SF				LF			LF 1660					LB			EA. 2	LB 293				EA.	EA.	LB						

TRAFFIC SIGN SUMMARY SHEET 16

PROJECT NAME: MONTGOMERY-WESTFIELD
PROJECT NUMBER: STP 2906(I)

FILE NAME: p10C190.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C190_97.1

PLOT DATE: 9/5/12
DRAWN BY: SJL
CHECKED BY: CDL
SHEET 97 OF 178