

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Rotation Direction	Maximum Banking	Design Speed
Tangent	POB	0+00.00	866592.821	1612410.951						
Tangent	PC	0+16.41	866603.871	1612423.082						
Arc	PC	0+16.41	866603.871	1612423.082	150	59.3	22°39'08.56"	Left	Match Existing	30
Arc	PI	0+46.45	866624.102	1612445.293						
Arc	CC		866714.764	1612322.074						
Arc	PT	0+75.71	866651.327	1612458						
Tangent	PT	0+75.71	866651.327	1612458						
Tangent	PC	0+93.02	866667.008	1612465.318						
Arc	PC	0+93.02	866667.008	1612465.318	1400	561.36	22°58'26.47"	Left	Match Existing	30
Arc	PI	3+77.52	866924.816	1612585.637						
Arc	CC		867259.083	1611196.678						
Arc	PT	6+54.38	867209.138	1612595.787						
Tangent	PT	6+54.38	867209.138	1612595.787						
Tangent	PC	8+53.79	867408.418	1612602.901						
Arc	PC	8+53.79	867408.418	1612602.901	320	198.6	35°33'31.81"	Right	NC	30
Arc	PI	9+56.40	867510.967	1612606.561						
Arc	CC		867397.002	1612922.697						
Arc	PCC	10+52.38	867592.263	1612669.176						
Arc	PCC	10+52.38	867592.263	1612669.176	642	113.19	10°06'06.91"	Right	NC	30
Arc	PI	11+09.13	867637.218	1612703.8						
Arc	CC		867200.520	1613177.803						
Arc	PT	11+65.58	867675.403	1612745.772						
Tangent	PT	11+65.58	867675.403	1612745.772						
Tangent	PC	13+34.73	867789.233	1612870.893						
Arc	PC	13+34.73	867789.233	1612870.893	3000	400.45	7°38'52.91"	Left	0.02	30
Arc	PI	15+35.25	867924.174	1613019.218						
Arc	CC		870008.311	1610852.058						
Arc	PT	17+35.18	868077.655	1613148.265						
Tangent	PT	17+35.18	868077.655	1613148.265						
Tangent	PC	20+06.19	868285.089	1613322.676						
Arc	PC	20+06.19	868285.089	1613322.676	420	346.59	47°16'52.36"	Right	0.08	30
Arc	PI	21+90.04	868425.806	1613440.992						
Arc	CC		868014.797	1613644.145						
Arc	PCC	23+52.78	868434.344	1613624.642						
Arc	PCC	23+52.78	868434.344	1613624.642	2000	227.45	6°30'56.96"	Right	0.08	40
Arc	PI	24+66.63	868439.630	1613738.364						
Arc	CC		866436.501	1613717.515						
Arc	PT	25+80.23	868431.978	1613851.952						
Tangent	PT	25+80.23	868431.978	1613851.952						
Tangent	PC	27+08.58	868423.350	1613980.019						
Arc	PC	27+08.58	868423.350	1613980.019	2000	333.14	9°32'37.53"	Left	0.036	40
Arc	PI	28+75.54	868412.127	1614146.598						
Arc	CC		870418.826	1614114.456						
Arc	PT	30+41.72	868428.679	1614312.732						
Tangent	PT	30+41.72	868428.679	1614312.732						
Tangent	PC	32+24.54	868446.803	1614494.645						
Arc	PC	32+24.54	868446.803	1614494.645	1200	242.53	11°34'48.60"	Right	0.053	40
Arc	PI	33+46.22	868458.866	1614615.727						
Arc	CC		867252.714	1614613.61						
Arc	PT	34+67.07	868446.378	1614736.766						
Tangent	PT	34+67.07	868446.378	1614736.766						
Tangent	PC	35+59.21	868436.921	1614828.42						
Arc	PC	35+59.21	868436.921	1614828.42	1250	343.99	15°46'03.18"	Left	0.052	40
Arc	PI	37+32.30	868419.157	1615000.597						
Arc	CC		869680.321	1614956.707						
Arc	PT	39+03.21	868448.848	1615171.122						
Tangent	PT	39+03.21	868448.848	1615171.122						
Tangent	PC	40+36.22	868471.664	1615302.163						
Arc	PC	40+36.22	868471.664	1615302.163	1300	276.93	12°12'19.72"	Left	0.05	40
Arc	PI	41+75.21	868495.505	1615439.096						
Arc	CC		869752.396	1615079.171						
Arc	PT	43+13.15	868547.758	1615567.893						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Rotation Direction	Maximum Banking	Design Speed
Tangent	PT	43+13.15	868547.758	1615567.893						
Tangent	PC	44+46.41	868597.854	1615691.372						
Arc	PC	44+46.41	868597.854	1615691.372	1825	676	21°13'22.26"	Right	0.042	40
Arc	PI	47+88.32	868726.394	1616008.207						
Arc	CC		866906.728	1616377.462						
Arc	PT	51+22.40	868731.523	1616350.085						
Tangent	PT	51+22.40	868731.523	1616350.085						
Tangent	PC	52+27.51	868733.099	1616455.177						
Arc	PC	52+27.51	868733.099	1616455.177	1500	56.1	2°08'34.68"	Left	0.02	40
Arc	PI	52+55.56	868733.520	1616483.229						
Arc	CC		870232.931	1616432.675						
Arc	PT	52+83.61	868734.990	1616511.245						
Tangent	PT	52+83.61	868734.990	1616511.245						
Tangent	PC	53+83.35	868740.214	1616610.851						
Arc	PC	53+83.35	868740.214	1616610.851	800	269.53	19°18'13.08"	Right	0.067	40
Arc	PI	55+19.41	868747.341	1616746.718						
Arc	CC		867941.313	1616652.755						
Arc	PT	56+52.88	868709.152	1616877.303						
Tangent	PT	56+52.88	868709.152	1616877.303						
Tangent	PC	57+78.93	868673.771	1616998.288						
Arc	PC	57+78.93	868673.771	1616998.288	1600	259.65	9°17'52.38"	Left	0.043	40
Arc	PI	59+09.04	868637.252	1617123.166						
Arc	CC		870209.451	1617447.385						
Arc	PT	60+38.58	868621.388	1617252.304						
Tangent	PT	60+38.58	868621.388	1617252.304						
Tangent	PC	61+22.46	868611.161	1617335.555						
Arc	PC	61+22.46	868611.161	1617335.555	1550	259.58	9°35'43.23"	Left	0.043	40
Arc	PI	62+52.55	868595.300	1617464.678						
Arc	CC		870149.597	1617524.54						
Arc	PT	63+82.04	868601.183	1617594.639						
Tangent	PT	63+82.04	868601.183	1617594.639						
Tangent	PC	65+04.34	868606.714	1617716.815						
Arc	PC	65+04.34	868606.714	1617716.815	4000	85.75	1°13'41.75"	Left	0.02	40
Arc	PI	65+47.21	868608.653	1617759.648						
Arc	CC		872602.621	1617535.915						
Arc	PT	65+90.09	868611.510	1617802.429						
Tangent	PT	65+90.09	868611.510	1617802.429						
Tangent	PC	66+88.83	868618.089	1617900.949						
Arc	PC	66+88.83	868618.089	1617900.949	1350	293.22	12°26'40.04"	Left	0.049	40
Arc	PI	68+56.01	868627.896	1618047.809						
Arc	CC		869965.089	1617811.001						
Arc	PT	69+82.04	868669.119	1618189.105						
Tangent	PT	69+82.04	868669.119	1618189.105						
Tangent	PC	72+03.09	868731.031	1618401.309						
Arc	PC	72+03.09	868731.031	1618401.309	900	601.3	38°16'47.41"	Right	Match Existing	40
Arc	PI	75+15.45	868818.515	1618701.164						
Arc	CC		867867.051	1618653.379						
Arc	PT	78+04.39	868701.428	1618990.744						
Tangent	PT	78+04.39	868701.428	1618990.744						
Tangent	PC	79+60.99	868642.728	1619135.923						
Arc	PC	79+60.99	868642.728	1619135.923	1100	419.23	21°50'12.16"	Left	Match Existing	50
Arc	PI	81+73.18	868563.187	1619332.643						
Arc	CC		869662.522	1619548.258						
Arc	PT	83+80.22	868562.527	1619544.834						
Tangent	PT	83+80.22	868562.527	1619544.834						
Tangent	PC	86+16.45	868561.792	1619781.057						
Arc	PC	86+16.45	868561.792	1619781.057	1600	183.17	6°33'			