

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			EARTHWORK SUMMARY
							1510				1510		CY	COMMON EXCAVATION	203.15	5	1505	CY	COMMON EXCAVATION
									60		60		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	6	54	CY	UNCLASSIFIED CHANNEL EXCAVATION
							610				610		CY	EARTH BORROW	203.30	7	1006	CY	STRUCTURE EXCAVATION
							640				640		CY	SAND BORROW	203.31	9	2565	CY	SUBTOTAL
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	15	CY	ROUND
									1010		1010		CY	STRUCTURE EXCAVATION	204.25	4	2580	CY	TOTAL FILL AVAILABLE
									590		590		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	3	0.75	-	REDUCTION FACTOR
							310				310		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	9	1935	CY	TOTAL FACTORED FILL AVAILABLE
							910				910		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	11	603	CY	TOTAL FILL REQUIRED
							50				50		CY	AGGREGATE SHOULDERS, IN PLACE	402.10	5	1332	CY	TOTAL WASTE
							4				4		CWT	EMULSIFIED ASPHALT	404.65	0.4			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
									1		1		EACH	REMOVAL OF STRUCTURE (5'-0" X 5'-0" X 55'-0" BOX CULVERT)	529.15	-			
									1		1		LS	PRECAST CONCRETE STRUCTURE (12'-0" x 7'-0" x 80'-0" BOX CULVERT)	540.10	-			
														BEGIN OPTION AA					
							60				60		LF	15" CSP .079 (2-2/3 X 1/2)	601.0011	-			
							60				60		LF	15" RCP CLASS III	601.0810	-			
														END OPTION AA					
									5		5		CY	STONE FILL, TYPE I	613.10	4			
									85		85		CY	STONE FILL, TYPE III	613.12	5			
							463				463		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
							520				520		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	EST			
							40				40		HR	FLAGGERS	630.15	EST			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							960				960		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	EST			
							960				960		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	EST			
									85		85		SY	GEOTEXTILE UNDER STONE FILL	649.31	5			
							60				60		SY	GEOTEXTILE FOR SILT FENCE	649.51	EST			
							20				20		LB	SEED	651.15	EST			
							75				75		LB	FERTILIZER	651.18	EST			
							0.3				0.3		TON	AGRICULTURAL LIMESTONE	651.20	EST			
							0.5				0.5		TON	HAY MULCH	651.25	EST			
							50				50		CY	TOPSOIL	651.35	EST			
							1				1		LS	EPSC PLAN	652.10	-			
							20				20		HR	MONITORING EPSC PLAN	652.20	-			

PROJECT NAME: SEARSBURG  
PROJECT NUMBER: STP SCRP(7)

FILE NAME: d10ci98\_for.ms.dgn  
PROJECT LEADER: K. UPMAL  
DESIGNED BY: B. MCADAMS  
QUANTITY SHEET 1

PLOT DATE: 19-MAR-2013  
DRAWN BY: B. MCADAMS  
CHECKED BY: A. KEMPTON  
SHEET 6 OF 35