

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
													BEGIN OPTION AA					
						47850				47850		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	28			
						47850				47850		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	28			
													END OPTION AA					
													BEGIN OPTION BB					
						47850				47850		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	28			
						47850				47850		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	28			
													END OPTION BB					
													BEGIN OPTION CC					
						175				175		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	4			
						175				175		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	4			
													END OPTION CC					
													BEGIN OPTION DD					
						45				45		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			
						45				45		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-			
													END OPTION DD					
						47850				47850		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	28			
						47850				47850		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	28			
						2050				2050		EACH	LINE STRIPING TARGETS	646.76	EST.			
							1080			1080		SY	GEOTEXTILE UNDER STONE FILL	649.31	12			
							7500			7500		SY	GEOTEXTILE FOR SILT FENCE	649.51	EST.			
							230			230		LB	SEED	651.15	EST.			
							1000			1000		LB	FERTILIZER	651.18	EST.			
							4			4		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
							5			5		TON	HAY MULCH	651.25	EST.			
						525				525		CY	TOPSOIL	651.35	11			
							10500			10500		SY	TEMPORARY EROSION MATTING	653.20	EST.			
						423.3				423.3		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
						824.5				824.5		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	EST.			
						140				140		EACH	REMOVING SIGNS	675.50	-			
						14				14		EACH	DELINEATOR WITH STEEL POST	676.10	-			
						1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
						620				620		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675				
						5				5		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.			
						14750				14750		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	187			
						280				280		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	6			