



STA 41+00.00

MATCHLINE

MATCHLINE

STA 46+50.00

- 621.215 HD STEEL BEAM GUARDRAIL, GALVANIZED W/ 8 FEET POST  
STA 43+50 TO 43+97 LT & RT  
STA 44+35 TO 44+48 LT  
STA 44+35 TO 44+64 RT
- 621.217 HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/ 8 FEET POST  
STA 43+97 TO 44+35 LT & RT
- 621.60 ANCHOR FOR STEEL BEAM RAIL  
STA 43+56 LT & RT  
STA 44+42 LT  
STA 44+58 RT
- 621.80 REMOVAL AND DISPOSAL OF GUARDRAIL  
STA 43+50 TO 44+37 LT  
STA 43+50 TO 44+64 RT
- DURABLE 4 INCH WHITE LINE (SEE OPTION AA)  
DURABLE 4 INCH YELLOW LINE (SEE OPTION BB)  
STA 41+00 TO 46+50 RT & LT
- DURABLE LETTER OR SYMBOL (SEE OPTION AA)  
STA 46+23 LT "SCHOOL"
- 646.602 TEMPORARY 4 INCH WHITE LINE, PAINT  
646.612 TEMPORARY 4 INCH YELLOW LINE, PAINT  
STA 41+00 TO 46+50 RT & LT

- 675.20 TRAFFIC SIGN, TYPE A  
STA 41+59 LT  
STA 43+89 RT  
STA 44+35 LT (2)  
STA 46+23 LT (2)
- 675.341 SQUARE TUBE SIGN POST AND ANCHOR  
STA 41+59 LT (2)  
STA 43+89 RT  
STA 44+35 LT  
STA 46+23 LT (2)
- 675.50 REMOVING SIGNS  
STA 41+59 LT  
STA 43+89 RT  
STA 44+35 LT (2)  
STA 46+00 RT (2)  
STA 46+23 LT (2)
- 676.10 DELINEATOR WITH STEEL POST  
STA 43+39 LT & RT  
STA 44+38 LT  
STA 44+69 RT
- 900.675 SPECIAL PROVISION  
(HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)  
STA 44+95 LT  
STA 45+50 RT



**SIGN LEGEND**

R	= REMOVE
S	= SALVAGE
N	= NEW
RET	= RETAIN
T&T	= THINNING & TRIMMING
B-B	= BACK TO BACK
EXISTING	-----
NEW	_____

PROJECT NAME:	SUDBURY - BRANDON	FILE NAME:	d10c204_bdr.dgn	PLOT DATE:	13-FEB-2013
PROJECT NUMBER:	STP 0158(3)	PROJECT LEADER:	K. UPMAL	DRAWN BY:	B. MCADAMS
		DESIGNED BY:	B. MCADAMS	CHECKED BY:	A. KEMPTON
		LAYOUT 5		SHEET	23 OF 137