STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in.)	SIGN DIMENSIONS HEIGHT (in.)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in.) 1.75 lb/ft 1.88	SQUARE STEEL (in.) 2.0 lb/ft 2.42	SQUARE STEEL (in.) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia. (in.) 3.0 lb/ft 1.3	TUBULAR ALUMINUM dia. (in.) 4.0 lb/ft 1.7	TUBULAR ALUMINUM dia. (in.) 4.0 MOD. lb/ft 1.7	FOUNDATION	TUBULAR STEEL dia. (in.) 3.0 lb/ft 7.6	TUBULAR STEEL dia. (in.) 3.5 lb/ft 9.0	TUBULAR STEEL dia. (in.) 4.0 lb/ft 10.8	TUBULAR STEEL dia. (in.) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL "SHSM" STANDARD HIGHWAY SIGNS AND MARKINGS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																								
SUDBURY																																				
~~43+80, R.T.~~ 43+79, R.T.	BRIDGE 4 VT73	1	6	8	0.33						1				~~6~~ 9.0			X															VD-701			E-134
~~44+35, L.T.~~ 43+06, L.T.	BRIDGE 4 VT73	1	6	8	0.33						1				~~6~~ 9.0			X															VD-701			E-134
	0730 1123 0080	1	6	10	0.42																												VD-700			E-138
~~46+29, L.T.~~ 45+08, L.T.		1	36	36	9.00						2					~~16.8~~ 15.0 15.0		X															S1-1 COLOR FYG	X		
	SCHOOL	1	24	8	1.33																												S4-3P COLOR FYG	X		
~~51+35, R.T.~~ 50+17, R.T.		1	30	30	6.25						1					~~10~~ 14.0		X															W1-2L	X		
	30 MPH	1	18	18	2.25																												W13-1P	X		
~~52+23, R.T.~~ 51+05, R.T.		2	18	24	6.00						2					~~10~~ 13.5 13.5		X															W1-8	X		
~~52+91, R.T.~~ 51+67, R.T.		2	18	24	6.00						2					~~10~~ 13.5 13.5		X															W1-8	X		
~~53+52, R.T.~~ 52+33, R.T.		2	18	24	6.00						2					~~18~~ 13.0 13.0		X															W1-8L	X		
												FT 0	FT 0	FT 0	FT 12	FT 80.5	FT 0		EA	LB 0	LB 0	LB 0		LB 0	LB 0	LB 0	LB 0								

TOTALS	SF	~~SF~~ SF OF TYPE A INSTALL	EA	SF		FT	FT	LB	EA	LB	EA	EA	LB
SHEET 1	78.8					0	135.5	0		0			
SHEET 2	~~87.9~~	37.91				0	~~92.5~~ 142.0	0		0			
SHEET 3	44.3					0	93.5	0		0			
SHEET 4	64.6					0	76.5	0		0			
SHEET 5	56.6					0	138	0		0			
SHEET 6	54.1					0	106	0		0			
SHEET 7	29.6					0	81	0		0			
SHEET 8	39.3					0	67	0		0			
SHEET 9	18.3					0	34.5	0		0			
PROJECT TOTAL	423.3					0	824.5	0		0			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: SUDBURY-BRANDON
PROJECT NUMBER: STP 0158(3)

FILE NAME: d10c204_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B. MCADAMS
TRAFFIC SIGN SUMMARY SHEET 2
PLOT DATE: 13-FEB-2013
DRAWN BY: C. LEACH
CHECKED BY: B. MCADAMS
SHEET 84 OF 137