STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																						REMARKS	SIGN DETAIL		
												FLANGED CHANNEL			SQUARE STEEL (in.)					TUBULAR ALUMINUM dia. (in.)				TUBULAR STEEL dia. (in.)				W-SHAPE STEEL FTG. SIZE									"SHSM" STANDARD HIGHWAY SIGNS AND MARKINGS	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
		EA	WIDTH (in.)	HEIGHT (in.)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	lb/ft 1.12	lb/ft 2.0	lb/ft 3.0	1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD. lb/ft 1.7	FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	24"	30"	WEIGH T	POST SIZE	SIGN FRAME REQUIRED				
SUDBURY											OPTION ITEMS																									
~~109+09, R.T.~~ 108+42, R.T.	9% HIDDEN DRIVES	1 1	30 30	30 30	6.25 6.25						2					~~21.5~~ 15.0 15.0		X																W7-1A VW-060	X	 94	
~~110+63, R.T.~~ 109+97, R.T.	$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1					~~6.5~~ 13.0		X																VR-023b		94	
~~110+96, R.T.~~ 110+33, R.T.		1	48	24	8.00						2					~~18~~ 13.0		X																W1-6L	X		
~~111+06, R.T.~~ 110+33, R.T.		1	48	24	8.00						2					~~18~~ 13.0		X																W1-6L	X		
~~118+14, R.T.~~ 117+65, R.T.	0730 1123 0220	1	6	10	0.42						1				~~5~~ 9.0			X																VD-700			E-138
~~120+11, L.T.~~ 119+61, L.T.	 35 MPH	1 1	30 18	30 18	6.25 2.25						1					~~10~~ 15.0		X																W1-4L W13-1P	X X		
~~126+46, L.T.~~ 125+90, L.T.	HIDDEN DRIVES	1	30	30	6.25						1					~~9.5~~ 15.0		X																VW-060		94	
~~128+83, L.T.~~ 128+20, L.T.	0730 1123 0240	1	6	10	0.42						1				~~5~~ 9.0			X																VD-700			E-138
~~135+59, R.T.~~ 136+35, R.T.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					~~9.5~~ 13.0		X																VR-017		94	

												FT 0	FT 0	FT 0	FT 10	FT 96	FT 0		EA	LB 0	LB 0	LB 0		LB 0	LB 0	LB 0	LB 0								
TOTALS	SF	~~SF~~ SF OF TYPE A INSTALL	EA	SF		FT													EA	LB									EA	EA	LB				
SHEET 1	78.8					0										135.5				0															
SHEET 2	37.9					0										92.5				0															
SHEET 3	44.3					0										93.5				0															
SHEET 4	64.6					0										76.5				0															
SHEET 5	56.6					0										138				0															
SHEET 6	~~54.1~~	54.01				0										~~106~~ 156.0				0															
SHEET 7	29.6					0										81				0															
SHEET 8	39.3					0										67				0															
SHEET 9	18.3					0										34.5				0															
PROJECT TOTAL	423.3					0										824.5				0															

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: SUDBURY-BRANDON
PROJECT NUMBER: STP 0158(3)

FILE NAME: dl0c204_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B. MCADAMS
TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 13-FEB-2013
DRAWN BY: C. LEACH
CHECKED BY: B. MCADAMS