STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS	SIGN DETAIL		
														SQUARE STEEL (in.)					TUBULAR ALUMINUM dia. (in.)				TUBULAR STEEL dia. (in.)				W-SHAPE STEEL FTG. SIZE										
		EA	WIDTH (in.)	HEIGHT (in.)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			1.75	2.0	2.5	ANCHOR	SLEEVE	3.0	4.0	4.0 MOD.	FOUNDATION	3.0	3.5	4.0	5.0	24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED		"SHSM" STANDARD HIGHWAY SIGNS AND MARKINGS	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
BRANDON											OPTION ITEMS																								
00+39, R.T.	Champlain St	1	48	12	4.00						2					11.0 ~~14~~ 11.0		X															D3-1		93	
10+78, L.T.	0730 1102 0020	1	6	10	0.42						1				~~10.0 5~~			X															VD-700			E-138
20+96, R.T.	~~40~~ MPH / 35 M.P.H.	1 1	30 18	30 18	6.25 2.25						1					20.0 ~~9.5~~		X															W1-2L W13-1	X X		
21+40, L.T.	0730 1102 0040	1	6	10	0.42						1				~~10.0 5~~			X															VD-700			E-138
25+01, L.T.	35 MPH	1 1	30 18	30 18	6.25 2.25						1					~~15.0 9.5~~		X															W1-2R W13-1	X X		
36+56, R.T.	35 MPH	1 1	30 18	30 18	6.25 2.25						1					~~15.0 9.5~~		X															W1-2R W13-1	X X		
44+21, L.T.	40 MPH	1 1	30 18	30 18	6.25 2.25						1					~~16.0 9.5~~		X															W1-2L W13-1P	X X		
53+00, L.T.	0730 1102 0100	1	6	10	0.42						1				~~9.0 6~~			X															VD-700			E-138

TOTALS	SF	SF OF TYPE A INSTALL ~~SF~~	EA	SF	FT 0	FT 0	FT 0	FT 15	FT 52	FT 0	[redacted]	EA	LB 0	LB 0	LB 0		LB 0	LB 0	LB 0	LB 0	EA	EA	LB
SHEET 1	78.8				[redacted]	0			135.5				0				0						
SHEET 2	37.9					0			92.5				0				0						
SHEET 3	44.3					0			93.5				0				0						
SHEET 4	64.6					0			76.5				0				0						
SHEET 5	56.6					0			138				0				0						
SHEET 6	54.1					0			106				0				0						
SHEET 7	29.6					0			81				0				0						
SHEET 8	~~39.3~~	39.26				0			~~67~~ 117.0				0				0						
SHEET 9	18.3				[redacted]	0			34.5				0				0						
PROJECT TOTAL	423.3					0			824.5				0				0						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: SUDBURY-BRANDON
PROJECT NUMBER: STP 0158(3)

FILE NAME: dl0c204_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B. MCADAMS
TRAFFIC SIGN SUMMARY SHEET 8

PLOT DATE: 13-FEB-2013
DRAWN BY: C. LEACH
CHECKED BY: B. MCADAMS
SHEET 90 OF 137