

PAVEMENT CORE DATA SHEET

#	TOWN	ROUTE	DIR/OS	MM	DEPTH IN.	PCC UNDER	OVER ASPHALT	DRAINABLE BASE	SOLID CORE	STRIPPED? WHERE?	SHOULDER CORE?	COMMENTS
1	SUDBURY	VT 73	WB	3.172	3	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 10" WITH 7" ASSUMED RECLAIM MATERIAL ON BOTTOM.
2	BRANDON	VT 74	EB	0.162	3.5	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 9" WITH 5.5" ASSUMED RECLAIM MATERIAL ON BOTTOM.
3	BRANDON	VT 75	WB	0.391	4.5	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 8.5" WITH 4" ASSUMED RECLAIM MATERIAL ON BOTTOM.
4	BRANDON	VT 76	EB	0.560	3	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 11.5" WITH 8.5" ASSUMED RECLAIM MATERIAL ON BOTTOM.
5	BRANDON	VT 77	WB	0.882	4	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 13" WITH 9" ASSUMED RECLAIM MATERIAL ON BOTTOM.
6	BRANDON	VT 78	EB	1.152	3.5	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 8" WITH 4.5" ASSUMED RECLAIM MATERIAL ON BOTTOM.
7	BRANDON	VT 79	EB	1.482	8	NO	YES	NO	YES	NO	NO	
8	BRANDON	VT 80	WB	1.592	2.75	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 10" WITH 7.25" ASSUMED RECLAIM MATERIAL ON BOTTOM.
9	BRANDON	VT 81	EB	1.690	5.5	NO	NO	NO	NO	YES, BOTTOM	NO	CORE DEPTH 10" WITH 4.5" ASSUMED RECLAIM MATERIAL ON BOTTOM.
				AVERAGE=	4.2							
				STD. DEV.=	1.7							

PROJECT NAME: SUDBURY-BRANDON
 PROJECT NUMBER: STP 0158(3)

FILE NAME: dl0c204_frm.dgn PLOT DATE: 13-FEB-2013
 PROJECT LEADER: K. UPMAL DRAWN BY: B. MCADAMS
 DESIGNED BY: B. MCADAMS CHECKED BY: B. KIPP
 PAVEMENT CORE DATA SHEET SHEET 95 OF 137